

ENSURE® MAX PROTEIN DON'T GIVE UP DELICIOUS FLAVOR TO GET GOOD NUTRITION



Ensure Max Protein has a 30g protein blend to feed muscles for up to 7 hours, and is a good source of 25 vitamins & minerals.



AVAILABLE IN 7 DELICIOUS FLAVORS: Milk Chocolate, French Vanilla, Creamy Strawberry, Creamy Peach, Cherry Cheesecake, Milk Chocolate with Caffeine,* and Café Mocha*





Use as part of a healthy diet.

Reference: 1. Nutrient data for 11-oz frozen mocha drink with whipped cream. FoodDataCentral. USDA website. https://fdc.nal.usda.gov. Accessed November 24, 2021.

* Milk Chocolate with Caffeine and Café Mocha flavors have 100mg of caffeine, as much as an 8-oz cup of coffee.

© 2024 Abbott 202316817(2)/January 2024 LITHO IN USA



A VIEW FROM THE PATIO

PULL UP A CHAIR, SIT BACK, RELAX, AND VIEW THE BACKYARD FROM OUR EYES.

hen I was growing up, the front porch was the place to be. It was somewhere to sit and chat with neighbors, read a book or just watch the world pass by.

As I grew up and got my own apartments in Chicago, I still clamored for that front-row seat to the neighborhood and would regularly hunker down on a concrete step or stoop. This, of course, was not as comfortable as a porch swing, but it was just as eye-opening.

These days, living in a 1920s home outside of the city, I've shifted my focus to the back-yard. Quiet. Serene. Nothing but me and the birds and trees. It's refreshing. Meditative, even.

Of course, the backyard opens up plenty of opportunities to create livable spaces. It's where you can create unexpected extensions of your home, and let activity flow freely from

inside to outside. I'm not talking about sunrooms. I mean real outdoor spaces.

At my home, this means a covered patio and a garden. For you, it could be a deck, terrace, porch, fire pit circle ... when it comes to using the sky as your ceiling, the sky truly is the limit. And that's exactly what this issue is all about.

Be ready to be inspired by outdoor living ideas—and even get your hands dirty if you feel like undertaking a project. Our team has created an original step-by-step plan for a porch swing. Want a project you can do in a weekend? Look no further than our how-to for building a table and chairs, perfect for a patio. And don't miss the chance to add a little ambience; we show you how to build planter boxes three ways.

Because having a solid foundation matters, you'll also learn




the ins and outs of maintaining and building a deck. Find out how to restore, repair and replace a deck, so no matter what state your wood is in (or what state your mind is in for doing some heavy lifting), you'll get some token advice.

Is gathering around a fire pit more your style? We have fire pit tricks and tips, instructions on how to build your own, and an homage to the Solo Stove.

One thing is certain: The time is ripe to get outside. And we're here for you, for every sunrise and sunset along the way.

KELLY AIGLON

DEPUTY EDITOR





FEATURES

DECK REPAIR MADE EASY Shabby surfaces? Bad boards? Turn an old deck into a like-new oasis.

PLANTER BOXES 3 WAYS Build them for your patio, window and railing.

DIY OUTDOOR

DINING ROOM A table and chairs that can be built quickly.

FIRE PITS: A PRIMER How to construct them for style and comfort.

HANDS ON

Discover our favorite new folding chair, mosquito repeller, workbench and more.

HANDY HINTS®

Clever solutions from our readers will help get your home in shape for spring.


BEST PRO TIPS

Yes, "petscaping" is a real thing. A pro landscape designer reveals how to make your garden dog-friendly and enjoyable for everyone.

HOME CARE

Are you ready to take on Operation: Organization? We have ideas to get your bathroom, kitchen and laundry room all tidied up.





- facebook.com/thefamilyhandyman
- pinterest.com/family_handyman
- youtube.com/thefamilyhandyman
- instagram.com/familyhandyman
- tiktok.com/@familyhandyman





TOP 5 PROJECTS YOU CAN DO IN A MORNING

here's nothing quite like the satisfaction of knocking out a project in a weekend. And if you can get the job done on a breezy Saturday morning? All the better.

That's the idea behind Saturday Morning Projects, a popular show streaming on the At Home with Family Handyman channel. Nina Bricko, a studio project editor for this magazine, contributes to the show, guiding you through quick, simple solutions that solve problems around your home—and, even better, increase its value. As a busy mom of two, Bricko has seen it all in her own home, whether it's cracked kitchen counters, peeling paint or bath toys that need a good organization. She shares her expertise and also takes you on the personal journeys of DIY enthusiasts just like you, who endeavor to improve their homes in a short time.


Got a single morning and DIY spirit? Try one of Bricko's favorite ideas from the kitchen episode:

- 1. Use paint to create a marbled look on your counters.
- 2. Create your own drawer with dividers from veneer plywood.
- 3. Build a sliding shelf under your sink and use it to hold trash and recycling bags.
- 4. Make an innovative spice rack with elastic bands that keep the spices in place.
- 5. Use a peel-and-stick backsplash for a fresh look and feel. Bricko offers some advice for those up to the challenge of taking a small but impactful project into their hands: "DIYers make mistakes—even the most skilled woodworkers," she says. "Whatever you do, don't give up. Just keep going and trying. Each build, no matter how small, brings out new skills in you. And most of what we do can be redone. So you might as well dive in and have some fun."

Stream Saturday Morning Projects on the At Home with Family Handyman channel on LG Channels, Samsung TV Plus and others.

BEFORE YOU CALL A PRO

With a little know-how, you wouldn't need to hire a pro for many household jobs. Get money-saving ideas and



up your skills with the help of our new book Before You Call a Pro. You'll benefit from 875-plus expert tips tailored for every skill level and space of your home. You'll be ready to tackle common repairs from quick, clever hacks to major renovation pointers—yourself. Get the book now for \$10. Shipping is free. Order at familyhandyman.com/C2403.

SHOW AND ... WE'LL TELL!

Are you proud of a recent shop project, home renovation or other DIY feat? Submit your photos and a brief description to us at familyhandyman.com submissions for a chance to be featured in our all-new Show & Tell department. We'll highlight DIY projects from builders and makers across the country and delve into the stories behind before-andafters that make you say "wow!"



WASHINGTON IDAHO Astoria Clarkston Mount St. Helens Hells Fort Hood River Clatsop Canyon Portland • Multnomah Pendleton Mt. Hood Falls OREGON

Your Columbia & Snake Rivers Cruise Includes:

- ★ 9-day/8-night exploration
- 8 ports of call with guided excursion options at each
- All onboard meals and our signature evening cocktail hour
- Full enrichment package with guest speakers and nightly entertainment
- * All tips and gratuities

Explore the Columbia & Snake Rivers

with the Leader in U.S. Cruising

Follow Lewis and Clark's epic 19th-century expedition along the Columbia and Snake Rivers aboard the newest ship in the region. Enjoy unique shore excursions, scenic landscapes, and talented onboard experts who bring history to life.



Gair today

866-975-1647

to request a free Cruise Guide

Small Ship Cruising Done Perfectly®

HANDS ON

TOOLS, GADGETS + GEAR WE RECOMMEND



he Helinox Chair One is an ultra lightweight seating option perfect for tailgating, camping or even packing with you on a hike. Coming in at 2.1 lbs. and sitting just 10 in. off the ground, it breaks down effortlessly, fitting into a compact pouch. Setup is also quick, thanks to a single internal bungee cord that self-assembles the poles. Once the frame is set, simply slip the ripstop polyester seat cover over the frame and take a seat.

Remarkably sturdy despite its size, the chair can hold up to 320 lbs., and I haven't had any issues with the aluminum frame bending or warping. However, as a taller woman, I do wish the back came up a little higher. If you are taller than average or simply prefer more support, the Helinox Chair Two, which features high-back support and weighs just 2.7 pounds, may be a better option.

The Chair One retails for \$110 on Amazon. It comes in six colors, and several accessories make the chair even more comfortable including a personal shade that offers sun protection and a ground sheet that prevents sinking on soft or uneven ground.

MARY HENN, ASSOCIATE SHOPPING EDITOR APPROVED





CREATE A NO-FLY ZONE FOR MOSQUITOES

Before I embarked on a family camping trip in Colorado, an outdoorsy friend clued me in to Thermacell products, which use a heat-activated repellent to establish a 15-to-20-ft. mosquito-free zone. The butane cartridge that powers the MR450—the model I tested lasts about 12 hours, and each repellent pad provides about four hours of protection.

The push-button ignition, while simple enough, took some fiddling: A faint sound was the only indication that the device was on. Fifteen minutes later, our campsite was buzzfree! The protective zone effectively covered our picnic table, stove, coolers and washing station, though when I left the campsite to use the restroom, mosquitoes quickly found me.

A spatial repellent like the Thermacell is great for when you're outside and mostly stationary (e.g., fishing or cutting wood) or if covering yourself in a spray-on repellent with DEET isn't an option, like at a backyard dinner party. Keep multiple options on hand for maximum protection. The Thermacell MR450 is available on Amazon for about \$33.

RYAN VAN BIBBER, EXECUTIVE EDITOR APPROVED



for the Family Handyman

8" x 13" Variable-Speed **Benchtop Wood Lathe**

For beginner woodturners

- >> Variable-speed spindle, 750-3200 RPM
- >> Knurled headstock and tailstock knobs for added grip
- >> Two interchangeable 41/4" and 7" tool rests
- Right-hand spindle ¾" x 16 TPI



9" Benchtop Bandsaw with Laser Guide and Quick Release

Portability with superior cutting performance

- » Rack-and-pinion table tilt
- Class II laser sight
- Fence adjustable for blade lead
- Adjustable wheels for alignment
- Extruded aluminum rip fence





G0803Z ONLY \$259

Hybrid Table Saw Perfect entry-level machine » Quick-release blade guard

- >> 30" Rip capacity
- Easy-glide fence system

10" 2 HP Open-Stand

- T-slot miter gauge
- >>> Precision-ground cast-iron table w/powder-coated steel extension wings



G0962 ONLY \$995

\$199 FREIGHT LOWER 48 STATES

1 HP Wall Hanging **Dust Collector**

Mounts to save shop space

- 30-Micron bag filtration
- Air suction capacity: 537 CFM
- >> 10" Cast aluminum impeller
- Steel base plate easily mounts to most walls
- >> Ideal point-of-use dust collector











Oscillating Edge Belt and Spindle Sander

Two sanders in one

- Quickly converts between sander types
- >> 0-45° tilting table
- 5 Sanding sleeves with matching inserts
- 3 4 Sanding drums
- » Built-in accessory storage





T27417 ONLY \$179



6" x 48" Belt/9" Disc Z Series Combo Sander

Use both horizontally & vertically

- Sanding belt tilts 90°
- >> Worktable mounts for use on disc or belt
- >> A-frame stand to minimize vibration
- Exclusive quick belt-release mechanism
- Scraphite-coated platen



G1014Z ONLY \$525



8" Benchtop Drill Press

Power & precision for hobbyists

- 5 speed ranges: 740-3140 RPM
- Drill through wood, metal, and even composites
- Adjustable depth stop
- >> 1/16"-1/2" Drill chuck
- ≫ 6½" Square cast-iron table



6" Benchtop Jointer

Compact for easy placement

- Straight-knife cutterhead with two SK5 steel knives
- >> Cast aluminum infeed and outfeed tables
- >> Infeed table height adjustment lock
- >> Built-in dust collection system with 21/2" dust port
- >> Table size: 61/4" x 30"



121/2" 2 HP Benchtop Planer

Award-winning planer

- Cutterhead speed: 10,000 RPM
 - Top-mounted return rollers
- >> 2-Knife HSS cutterhead
- Convenient carry handles
- >> Feed rate: 32 FPM



G0505 ONLY \$465



#GRIZZLYTOOL5



Please visit grizzly.com for up-to-date pricing.

Due to rapidly changing market conditions, our advertised prices may be changed at any time without prior notice.

WARNING! †1: Cancer & Reproductive Harm Some products we sell can expose you to chemicals known to the State of California to cause cancer

and/or birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov



GET HOOKED ON STAY-PUT MAGNETS


If you need a quick and versatile storage solution, look no further than Gator Magnetics. We tested out several of Gator Magnetics' storage hooks and found them to be incredibly convenient for hanging tools, decorations, materials and more. The hooks can hold a surprising amount of weight (Gator's Mega models hold up to 45 lbs.), and you can easily attach the hooks wherever they would come in handy—on a toolbox, metal shed, work truck, or even the side of your washing machine. The hooks

require no drilling or installing of permanent fixtures, so they can easily be moved around to rearrange a space. These little powerhouses are both func-

tional and stylish, providing a clutter-free alternative to traditional storage methods. Check them out at gatormagnetics.com.

SAMUEL ROSENMAYER, PROJECTS EDITOR/BUILDER APPROVED





PULL UP STUBBORN SHRUBS

Like every homeowner, I have unwanted trees and shrubs that have taken root in my yard. With Brush Grubber's Handy Grubber, I can handle the problem before the invaders get out of control. The handheld tool extracts small trees, woody weeds and shrubs with stems up to 1 in. in diameter. It's made from heavy-duty steel, with powerful spring-loaded gripping teeth that grab the offending stem. To operate the Handy Grubber, first open the jaws by pulling back the lever, then place the grips on the tree's trunk, close to the ground. Lastly, pull on the large D-ring-shaped handle. It's that simple.

easily pulled $\frac{1}{4}$ -to- $\frac{1}{2}$ -in. shrubs, and I'm confident that stronger users will be able to pull larger brush. But depending on the soil conditions and maturity of the plant, this tool may not work for extracting every pesky thing in your yard. (Note: Extracting trees and roots is much easier if the ground is sufficiently moist.) That said, when the Handy Grubber works, it works very well. I would never be able to pull by hand what this tool does in two seconds. When the next generation of seedlings appears, I'll be ready. The Handy Grubber is available at Walmart and on Amazon for under \$70.

SHERI KAZ, ASSOCIATE SHOPPING EDITOR APPROVED

TOTE AROUND A HEAVY-DUTY WORKBENCH

They say time is money, and the Keter Folding Work Table has saved me time in spades. The portable workstation—which comes fully assembled—can be unfolded, locked in place and ready to use in less than 30 seconds. You can use it as a miter saw stand, to secure boards for cutting or painting, or for whatever projects are on your to-do list.

The table's standout features are the guide rails integrated into the worktop and the set of two 12-in. ratcheting clamps that can be mounted vertically or horizontally to secure a workpiece. A lower shelf offers storage for tools or other supplies, such as a power strip. The heavy-duty plastic resin construction can handle up to 1,000 lbs., yet the table is still light enough to load onto a truck. And when the job is over, it folds into a 4½-in.-thick briefcase shape with an ergonomic handle—a big convenience for transport and storage. I highly recommend the Keter Folding Work Table as a portable clamping table and as a work stand for power tools. Find it online on Amazon or Wayfair for \$110. fh

CATHY HARMS, PRO WOODWORKER APPROVED







Choose customizable coverage options that work for you and your wallet—and keep your truck and business rolling.

Visit ProgressiveCommercial.com or call your local agent.

PROGRESSIVE COMMERCIAL

HANDY HINTS

CLEVER SOLUTIONS FROM OUR READERS





BACK-BREAKING WORK REQUIRES SOME HELP

Everyone feels aging pain, but CBD can help

By: Beth Giles

ife really does fly by. Before I knew it, my 60s had arrived, and with them came some new gifts from dear ol' Mother Nature—frequent knee pain, stress, low energy and sleeplessness. Now, I'm a realist about these things, I knew I wasn't going to be young and springy forever. But still, with "golden years" nearly on my doorstep, I couldn't help but feel a little cheated. That is until I found my own secret weapon. Another gift from Mother Nature.

It began a few months back when I was complaining about my aches and pains to my marathon-running granddaughter, Jen. She casually mentioned how she uses CBD rub to help with her joint pain. She said that CBD gave her more focus and clarity throughout the day and that her lingering muscle and joint discomfort no longer bothered her. She even felt comfortable signing up for back-to-back marathons two weekends in a row this year. That made even this self-proclaimed skeptic take notice.

But I still had some concerns.
According to one study in the Journal of the American Medical Association, 70% of CBD products didn't contain the amount of CBD stated on their labels. And, as a consumer, that's terrifying!

If I was going to try CBD, I needed to trust the source through and through. My two-fold research process naturally led me to Zebra CBD.

First, I started calling my family and friends. Call me old fashioned but I wanted to know if there were people whom I trusted

(more than anonymous testimonials) who've had success using CBD besides my granddaughter.

Secondly, I wanted cold hard facts.
Diving deep into the world of CBD research and clinical studies, I came across Emily Gray M.D., a physician at the University of California at San Diego (UCSD) Medical School and medical advisor to Zebra CBD who is researching the effects of CBD.
Dr. Gray wrote "early results with CBD have been promising and we have a lot of research underway now. I've had several patients using CBD with good success. It's important that you know your source of CBD and how to use it properly."

After hearing it from the doctor's mouth, I returned to my research, asking more people and was amazed by the number of close friends and family who were already on the CBD train. Apparently, I was the only one without a clue! And funny enough, a couple of friends who commented were using the same brand as my granddaughter—Zebra CBD. There was no consensus as to why they were using CBD, but the top reasons given were for muscle & joint discomfort, mood support, sleep support, stress and headaches, as well as supporting overall health & wellness.

Eventually, even the most skeptical of the bunch can be won over. With a trusted CBD source in mind, I decided to give it a go.

When I viewed Zebra CBD's selection online, I was impressed by its array of products, including CBD oils called

tinctures, topicals, chewable tablets, mints and gummies. After reading on their website that all their products are made with organically-grown hemp, I ordered... and it arrived within 2 days!

The first product I tried was the Rub.

Now this stuff was strong. Immediately after rubbing it on my knee, the soothing effects kicked in. It had that familiar menthol cooling effect, which I personally find very relieving. And the best part is, after two weeks of using it, my knee pain no longer affected my daily mobility.


The Zebra Sleep Gummies, on the other hand, had a different but equally positive effect on my body. To take it, the instructions suggest chewing thoroughly. This was simple enough, and the taste was, well, lemony. After about 15 minutes, a sense of calm came over my body. It's hard to describe exactly; it's definitely not a "high" feeling. It's more like an overall sense of relaxation—and then I fell fast asleep. Needless to say, I slept great and woke up refreshed. I haven't slept like that in a long time.

While it hasn't been a catch-all fix to every one of my health issues, it has eased the level and frequency of my aches. And it sure doesn't seem like a coincidence how rejuvenated I feel.

All-in-all, CBD is one of those things that you have to try for yourself. Although I was skeptical at first, I can safely say that I'm now a Zebra CBD fan and that I highly recommend their products.

Also, I managed to speak with a Zebra CBD spokesperson willing to provide an exclusive. If you order this month, you'll receive \$10 off your first order by using promo code "**FH10**" at checkout. Plus, the company offers a 100% No-Hassle, Money-Back Guarantee. You can try it yourself and order Zebra CBD at ZebraCBD.com/FH or at 1-888-762-2699.

HANDY HINTS



DIY PADDED VISE

Holding odd-shaped parts in a bench vise is tricky. When I need to sand or file an odd-shaped part, I sandwich it between two pieces of rigid foam in the vise. This solidly holds the part without marring it.

ANNE OF ALL TRADES



MAKE DURABLE SANDPAPER FOR TIGHT SPACES

I do a lot of finish-sanding free-hand, without a sandpaper block, so I can smooth edges and get into nooks and crannies. But the finer grits are usually bonded to thin paper. For me, the paper is too thin and tears long before the grit wears out. So I apply duct tape to the back of the sandpaper. The sandpaper is still flexible enough to sand a tight radius and it's far more durable. You can use this super-strong sandpaper like a shoeshine rag.

CHUCK MERCHANT



Over time showerheads can become clogged and not spray at full power because of mineral deposit buildup. An easy way to unclog your showerhead is to fill a resealable plastic bag with white vinegar and submerge the showerhead in the vinegar-filled bag. Secure the bag to the showerhead with a rubber band. Allow it to soak for a couple of hours, then remove the bag. Rinse off the showerhead with water and wipe with a clean cloth.

SAM TURNER



HOW TO ADJUST TIGHTLY SPACED PAVERS

If you have pavers or bricks close together, you know how hard it can be to lift one of them without disturbing the entire herd. I came across this tool when I was fine-tuning a patio with tightly spaced pavers, and it really came in handy to adjust some flagstones following frost heaves. The tool is advertised online for radiator hose removal. But the narrow shank and 90-degree bend at the end makes it ideal for hooking underneath a paver or stone without disturbing or displacing adjacent pieces. fb

PATRICK EICHER

This Necklace is NOT for Sale ... It's yours for FREE*

No kidding. Only Stauer can give you 200 carats of genuine amethyst for NOTHING.

You may think you understood the concept of "priceless" jewelry. For years, "priceless" meant "astronomically expensive." That is, until now ...



Stauer smashes the luxury status quo with the release of our FREE* 200-Carat Lusso Amethyst Necklace. That's right, we said FREE ... as in "priceless." No charge.* ZERO dollars.* Call now and we'll send you this impressive helping of genuine amethyst (independently appraised at \$295) for FREE. We cut the price 100%. You only pay \$24.95, our regular charge for shipping and processing. We'll even pay you back with a

\$30 discount certificate — that's our Better Than Free Shipping!

A collection of purple perfection. Your Lusso Amethyst Necklace is a 200-carat symphony of smooth purple genuine gemstones.

Each gemstone's shape and translucence ignites the velvety, violet hues. The polished amethysts are hand-strung on double-knotted jeweler's thread, and the stunning 18" necklace

(with 2" extender) secures with a gold-

finished lobster clasp.

Too good to pass up. Too good to last long. Amethyst is one of the world's most coveted gemstones and our supply is extremely limited. We can only offer such an outrageous deal for a short time every few years. Over 30,000 thrilled customers were lucky enough to get this promotion last time.

We only have about 2,500 left in stock. Act now!

Necklace Specifications:

- 200 ctw of genuine amethyst
- Gold-finished spacers
- 18" + 2" length necklace

Lusso Amethyst Necklace:

Lusso Amethyst Necklace (200 ctw) \$249** FREE*

*Pay only shipping & processing of \$24.95. Special price only for customers using the offer code.

1-800-333-2045

Your Insider Offer Code: LAN517-05

200 carats of pure luxury independently appraised at \$295[†]... yours FREE!*

> "This necklace is beautiful. I could not believe my eyes ... **GREAT!**"

— Bonnie from Longs, SC

FREE AMETHYST NECKLACE LIMITED TO JUST THE FIRST 2,500 RESPONDERS TO THIS AD!

* This offer is valid in the United States (and Puerto Rico) except in TX, FL, CO, OK, RI, NH, WV, OR, SC, VA, CA and ID. These state residents will be charged one cent (\$.01) + shipping & processing for the item. Void where prohibited or restricted by law. Offer subject to state and local regulations. Not valid with any other offers and only while supplies last. This offer is limited to one item per shipping address. ** Free is only for customers using the offer code versus the price on Stauer.com without your offer code. † For more information concerning the appraisal, visit www.stauer.com/appraisedvalues.asp.

Stauer, 14101 Southcross Drive W., Ste 155, Dept. LAN517-05, Burnsville, MN 55337 www.stauer.com



REPLACEA BAD BOARD

Even if your deck has seen better days, a complete rebuild probably isn't necessary. Replacing problem boards is faster and cheaper. Whether you have one problem spot to replace or many, the process is the same.

Using a jigsaw, cut the bad section of board free from the joists at both ends. Mark and cut alongside the joist using a Speed square as a guide.

When determining where to cut out the board, keep these guidelines in mind:


- Splices should be offset by at least one joist space.
- New boards should be supported by three joists or cleats.
- If possible, stagger splices over four or more rows of boards.
- Mark the replacement boards before cutting—weaving the splices can be a puzzle.

PULL NAILS, REMOVE BOARD AND FASTEN CLEATS

Remove any nails still holding down the board by driving a cat's paw into the wood under each nail head and pulling back on the handle. If the nail head pulls off, grab the nail shank with locking pliers.

Remove the bad board as well as any deck fasteners stuck in the joists. Then install cleats to support the ends of the new board. Fasten 12-in.-long cleats to the joists after pulling them up against the bottom of the adjacent deck boards.

INSTALL FLASHING Before installing the new board, place a piece of flashing tin on top of the cleat. If possible, lift the abutting board slightly and slide the flashing underneath it as well. The flashing keeps water from standing





on the cleat-joist seam, preventing future joist rot.

INSTALL NEW BOARD Using the same material as the rest of the deck, cut a length to fit the opening. Leave α $^{1}/_{16}$ -in. gap between the boards to allow the ends to dry when they get wet. Position the board, drill pilot holes and fasten the board to the joists. Use the same spacing and fasteners as you used on the rest of the deck.





WHAT IT TAKES

TIME 1-2 hours

SKILL LEVEL Beginner

COST Varies

TOOLS

Cat's paw, circular saw or miter saw, cordless drill/driver, extension cord, hammer, hearing protection, jigsaw, locking pliers, nail set, pry bar, safety glasses, sawhorses, Speed square, tape measure

MATERIALS

Deck boards, galvanized nails and screws, flashing tin

RESTORE A SHABY SURFACE

Even if you stain or seal your wood deck, the boards can still crack and splinter, making the surface look old and worn. That's where deck paint restoration products come in, if you're up to doing some handiwork.

These coatings are thick enough to fill all cracks, knotholes and splinters in your deck. They provide a new textured surface that can last more than a decade without additional applications. And, as icing on the cake, you can do the prep work in one day, then apply the coating over a two-day period the following weekend.

MAKE SMALL REPAIRS

Break off any large splinters.
Then reset any protruding
nail heads, or remove them and
secure the boards with deck
screws instead. Be sure you
have replaced any bad boards
with new decking (follow the
process outlined on pg. 15).


As you tighten any screws that have backed out, they may break off. If this happens, pull out and replace the old screws.

O PREPARE THE DECK FOR PAINTING

Use an orbital sander with 80-grit sandpaper on any old paint or finish that's peeling or chipped. If you've applied a solid stain or clear sealer and then covered areas of the deck with planters or furniture, those sun-shielded areas must be sanded to rough up the surface.

Dilute the manufacturer's recommended deck cleaner, apply it and let it soak in for the recommended time. Then scrub the entire deck with a stiff scrub brush and extension handle.


Pay attention to any greasy areas; get all the grease off. Then power-wash the deck to remove





ground-in dirt and loose stain.
Aim the nozzle into the board
gaps to clean them out as well.
Be careful: Too strong of a stream
can damage the wood's surface.

Before applying the restoration product, let the wood dry completely and mask off any surface you want to protect from the paint, such as siding or bushes.





WHAT IT TAKES

TIMEMultiple
days

SKILL LEVEL Intermediate **COST** Varies

TOOLS

6"stain brush, drill/driver, pressure washer, roller extension pole, roller screen, safety glasses, special application rollers, stiff scrub brush, orbital sander

MATERIALS

Deck restoration coating, manufacturer's recommended deck cleaner, masking tape, paint stir sticks, plastic sheeting, 80-grit sandpaper

START WITH THE RAILING

Stir the coating and begin coating the railings. Start with the balusters and the posts, then move to the rail. At this stage, also cut in the coating into the corners of the deck at the base of the posts and balusters.

ROLL ON THE DECK COATING

Use a roller screen made to hang onto the side of the 5-gallon bucket to limit unwanted drips as you roll the coating right from the bucket onto the deck boards. Then lift, reload and do the next section.

7 BRUSH THE COATED **BOARDS AND FILL GAPS**

Roll the entire length of the deck boards a few rows at a time. Once you've rolled a few rows of boards, switch to a 6-in. stain brush and glide it over each of the coated boards, all the way across in one stroke. A brush with a threaded handle can be attached to an extending paint pole so you can reach into the corners.


As you're rolling, take notice of areas the coating doesn't fill in completely. If you come across any knots, nail holes or cracks that aren't filling up, load up a brush and drip it in to fill the gaps.

Clean up with soap and water and let the first coat dry to the touch. Apply the sec-


ROLL ON A SECOND COAT


dry for three to six hours, or until ond coat using the same method. Then let the deck dry for two full days before walking on it. For the longest-lasting result, clean the coating in the spring and fall using the manufacturer's recommended cleaner.

Note: You probably won't like the look of the first coat. Don't worry—the second coat is the "magic coat" that fills in all the gaps and provides the smooth texture you saw at the store.









DECK RESURFACERS 101

Deck paint restoration coatings, also known as deck resurfacers, are composed of a long-lasting tintable acrylic base material with UV inhibitors and added solids (aluminum oxide or sand). The solids provide texture and hold the product together, like aggregate in concrete.

Some brands allow the wood to breathe yet repel water, while others form an impermeable barrier. Some work on vertical surfaces as well as the decking surface. Coverage ranges from 20 to 75 sq. ft. per gallon.

All brands require rigorous surface preparation and application methods. The procedures vary by manufacturer—use our process as a starting point, and always read the product label!

Choose a color carefully, because deck restoration coatings absorb a lot of heat and retain it longer than plain wood. If you pick a dark color and your deck receives direct sunlight, it may be too hot to walk on with bare feet.

REPAIR A WOBBLY RAILING

A wobbly railing isn't just an annoying quirk of an aging deck—it's a safety concern worth addressing before warmer weather arrives. There are a few usual suspects when it comes to the wobble, and most can be fixed in a day.

TIGHTEN LOOSE BOLTS
From beneath the deck,
tighten any loose bolts. If
the post doesn't have any bolts,
add them.

REPLACE STUCK CARRIAGE BOLTS WITH HEX HEADS

A carriage bolt that spins in place when you try to tighten it needs to be replaced. To do so, first spin two nuts on the end of the bolt, then tighten them together using two wrenches. Grab the stuck nut with one wrench and the nut nearest the end with the other. Then work the rusted nut loose. A shot of penetrating oil can help get it to move.


Remove the old carriage bolt and replace it with a hex-head bolt of the same diameter. Now you can turn the nut and hold the bolt still to tighten the post.

FIX RAILING GAPS


To fix any gaps in railings or even loose railing, start by disassembling it. Sometimes all it takes is tightening up a few screws. If the handrail is too soft to tighten, however, it will need to be replaced. Mark where the parts are lined up on the post, then remove them. Measure and cut new parts to fit and match the rest of the rail, then line up the apron with the marks on the post and toe-screw it into place. Fasten the top rail from below.

ADD BLOCKING

Cut pressure-treated 2-by blocking (the same width as the floor joists) to fit tightly between the rim joist and the next joist. Place the blocking









directly behind the post and toescrew it into both the rim joist and neighboring joist. Fasten additional blocking every 4 ft. along the rim joist.

PRO TIP

Deck posts and railings screwed to a single rim joist feel wobbly because the rim joist flexes when you lean against the railing. Adding blocking stiffens the rim joist.

WHAT IT TAKES

TIME SKILL LEVEL COST
2-3 Beginner <\$100
hours

TOOLS

Wrenches, circular saw, drill/driver, spade bit

MATERIALS

Pressure-treated 2-by (match the joist size); 3-in. deck screws; 2x4 (to match the railing); ½" carriage bolts, nuts, and washers; ½" hexhead bolts; spray penetrating oil



STOPS ADR FIELD AND BRUSH MOWER

- Up to 2X the power of the competition
- Cut 3" thick brush and tall field grass with ease
- Widest selection of deck sizes and features
- Go-anywhere power steering and hydrostatic drive options
- Tow-Behind, Commercial, and NEW Electric models available

STARTING \$ 1,99999

PROMAX34

Assembled in the USA

Assembled in the USA using domestic and foreign parts.

DR® is the Leader in Leaf Vacs

Tow-Behind

- #1 in vacuum power and capacity
- New PRO MAX model holds up to 450 gallons
- All models newly redesigned with up to 20% more capacity

Walk-Behind

- NEW PILOT XT models fill paper leaf bags for curbside pickup
- Collects and mulches up to 50 lbs.
 of leaves per bag
- Includes onboard caddy for extra bags



Do it Right with DR® Power Equipment

Scan the code to visit GoDRPower.com to shop or request a free catalog!

Toll-free: 800-456-2068 | Free Shipping on orders over \$100



Everything You Need for Spring Clean-up!

Haul up to 800 lbs. with a DR® Powerwagon

- Self-propelled hauler
- Powers up hills with ease
- Powered dumping
- Converts to a flatbed

Make stumps disappear fast with a DR® Stump Grinder

- 3-sided Greenteeth[®] tungsten carbide-tipped teeth that last 3X longer
- Powerful engines that take 372 "bites" per second through even the toughest hardwoods
- Self-propelled and electric start available

Burn Safely with a DR[®] BurnCage™


- Perforated stainless steel maximizes airflow
- Light, durable, and folds flat for storage
- Traps embers and burns more thoroughly
- Available in 3 sizes











Make Your Driveway Like New with a DR® Power Grader

- Fill in potholes and smooth out washboard
- Loosen and redistribute existing material
- Tow with your ATV, UTV, or tractor

Great Gardens Start with DR® Rototillers

- Easily bust sod and churn through compacted soil
- Prepare seedbeds or till garden waste back into your soil
- Full line of walk or towbehind models and nimble cultivators

Devour Brush Piles with a DR® Chipper Shredder

- Chip and shred with power to spare
- Bigger engines that chew up the competition
- Built USA tough for smooth, reliable operation







Scan the code to visit **GoDRPower.com** to shop or request a free catalog!







THIS SWING'S SMOOTH, GENTLE GLIDE WILL KEEP YOU DAYDREAMING FOR HOURS. BETTER YET, YOU CAN BUILD IT IN A WEEKEND.


BY FAMILY HANDYMAN EDITORS

imple cuts and a no-hassle glue-andscrew assembly technique make this swing a great first-time woodworking project. We designed the swing with a unique suspension system made from ½-in. galvanized steel pipe slipped through the

swing frame to act as a cradle and eliminate stress on wood joints. We then fastened eye bolts through the steel pipe and covered the pipe ends with soft rubber caps to prevent scrapes. Welded steel chain supports the swing assembly, securely fastened to solid framing in the porch roof.

A WORD ON WOOD

When selecting a wood for this project, stay away from cedar, redwood and soft pine. They'll mar easily and they won't hold screws as well as other, denser woods. Instead, go with fir, southern yellow pine, cypress, poplar, white oak or maple. Oak and maple are harder to cut, sand, drill and screw, so avoid them if you're a first-timer. We chose poplar because it's strong, readily available, easy to work with and takes paint well.



CUTTING LIST

KEY QTY. DIMENSIONS PART A1 34" x 5½" x 17½" Side seat braces A2 34" x 5½" x 15½" Center seat brace 34" x 3½" x 10½" Front arm braces В 3/4" x 31/2" x 43" Front stringer 34" x 3½" x 40" Rear stringer D 34" x 3½" x 40" Lower back brace 3/4" x 25/16" x 43" F Center back brace 34" x 1½" x 40½" G Top back brace 34" x 5½" x 35" Center back slats Н 3/4" x 2¹1/16" x 35" Back slats K 34" x 113/16 x 35" Tapered back slats 34" x 2½" x 10½" Arm supports Horizontal arm supports 34" x 3" x 221/4" M 34" x 211/16" x 41 1/2" Seat slats Ν P 34" x 51/2" x 27" Arms 1/2" (13/16" outside diameter) x 56" Steel pipe 1/2" (13/16" outside diameter) x 51" Steel pipe R

MATERIALS LIST

ITEM	QTY.
½" galvanized pipe (no threads)	51"
½" galvanized pipe (no threads)	56"
1¼" galvanized deck screws	2-lb. box
1%" galvanized deck screws	2-lb. box
4" x ¾" closed eye screws	2
3/16" welded steel chain (zinc-plated or galvanized)	20 ft.
1x4 x 8' boards (poplar)	3
Construction adhesive	4 oz.
1x6 x 8' boards (poplar)	7
2¼" quick-link eyes	8
2½" pan head screw	1
¼" eye bolts	4
2" #8 sheet metal screw	1
¾" rubber caps	4
4" x ¼" lag screws	12
100- and 150-grit sandpaper	



CUT SLATS

Using a table saw, make eight 1×3s by ripping four 1×6 boards to $2^{11}/_{16}$ in. Cut the boards to length for the seat (N) and back slats (J).


Mark a diagonal taper onto a 1×3 (see Photo 1). Use a jigsaw to cut along the line, making the two outer slats (K). Use a block plane to smooth the cut edges.


RIP BACK BRACES Set your saw at 27½ degrees and rip the pieces that make the center (F) and top back braces (G).


CUT CURVED PIECES Toraw a 1-in. grid directly on the wood for the side (A1) and center seat braces (A2) and arms (P) (see Figure A). Use the grid to copy the curves. Clamp the seat support parts to the workbench as you cut the curves with a jigsaw. Sand along the curves with 100-grit sandpaper. Use a sharp spade bit to drill ⁷/₈-in.-dia. holes into parts Al and A2 for the front pipe hanger.


ASSEMBLE FRONT ARM SUPPORTS


Notch the front arm braces (B) with a jigsaw to accept the front stringer (C). Drill pilot holes and countersink them. Apply a dab of construction adhesive at each joint. Fasten with 15/8-in. deck screws.



















ATTACH REAR STRINGER

Trace the angle of the center seat brace (A2) onto each side seat brace (A1) to get the proper positioning of the rear stringer (D) fastening points. Again, drill pilot holes and glue and screw the seat braces to the front stringer and the front arm braces. Next, glue and screw the rear stringer to the seat braces.

FASTEN THE BACK SLATS

Lay all the back slats face down on a flat surface and slip temporary 1/4-in. spacers between the slats. Fasten the bottom brace (E) to the middle slat, using a framing square to ensure they're joined at 90 degrees.

7 CUT THE TOP CURVES

Trace the top curves on the front side of the back assembly using a homemade beam compass. Nail one end of the compass 14 in. from the top and in the center of the 1×6 back slat. Insert your pencil into the 1/4-in. hole drilled in the other end of the compass. Cut along the mark with your jigsaw.

JOIN THE BACK AND SEAT ASSEMBLIES

Hang the lower part of the back assembly over the edge of your work surface to make room as you slide the seat assembly onto it. Align the rear stringer of the seat assembly with a mark drawn $2\frac{1}{2}$ in. from the bottom of the back assembly. Glue the joint, then clamp and screw the assemblies together.

FIT THE PIPES

Cut and drill the pipes (Q and R) and slide them into the holes. File the inside of the $^{7/8}$ -in. hole in the arm support (M) with a coarse half-round file if the support pipe won't easily slide through. The rear support pipe should fit snugly under the center back brace (F) as it protrudes through each arm support.

Meet the Hybrid That Never Needs Gas

A one-of-a-kind timepiece for the Impossible Price of \$39!

Impossible Price

Innovation is the path to the future. Stauer takes that seriously. That's why we developed Lthe Yellowjacket Hybrid Watch, an impressive timepiece that's sure to turn heads. We originally priced the Yellowjacket at \$399 based on the market for advanced sports watches ... but then stopped ourselves. Since this is no ordinary economy, and everyone else has raised their prices, we decided to start at 90% OFF! This technological marvel can be yours for ONLY \$39! Only Stauer can offer you a price this good.

When it comes to purchasing a quality, timeless timepiece, there's one question every prospective buyer must consider: digital or analog. Both have their advantages. We say, why not have both?

Our Men's Yellowjacket Hybrid Watch is a surprising innovation. Its digital readout is powered by a precise quartz engine that combines both analog and digital timekeeping. Outfitted with a stopwatch, alarm, a.m./p.m. settings and day, date and month complications, this timepiece is hard to beat.

With its large face and handsome, masculine design, this watch is perfect for the back nine and the happy hour afterward. Water-resistant up to 3 ATM, this timepiece won't wimp out if it has a run-in with a water hazard. And best of all is the color of its case and band: This watch boasts two tones.

Lately, two-tone watches have been the toast of the luxury watch world: "Two-tone is the physical embodiment of work-hard, play-hard," says Hodinkee, a website that chronicles the watch industry. But where luxury brands are charging hundreds simply for their two-tone watch bands, we're asking JUST \$39 for an entire two-tone watch!

Act now! We only have 1,237 731 available for this ad, and half have already sold! And if this watch doesn't live up to your expectations for some reason, return it for a refund with no questions asked.

Watch Specifications:

- Precision movement
- Two-tone stainless steel band
- Stopwatch, alarm, a.m./p.m. settings and day, date and month complications
- Water-resistant to 3 ATM

Men's Yellowjacket Hybrid Watch \$399

\$39* + S&P Save \$360

*You must use Insider Offer Code: YHW161-01 to get this price.

1-800-333-2045


Your Insider Offer Code: YHW161-01


"Love the style and the

combo of analog and digital!" - Rich C., Plainfield, IL


JOIN MORE THAN I MILLION SMART PEOPLE WHO LOVE THEIR STAUER WATCHES


Stauer, 14101 Southcross Drive W., Ste 155, Dept. YHW161-01, Burnsville, MN 55337 www.stauer.com











ADD SCREWS FOR STOPS
Drill a 3/16-in. ho

Drill a ³/₁₆-in. hole in the center of the rear support pipe, then screw a 2-in. #8 sheet metal screw (use a ¹/₈-in. pilot hole) up into the center back support. This connection will keep the pipe from sliding to one side while the swing is swinging.

With the pipes in place, drill a 9/32-in.-dia. hole 1 in. from the end of each pipe for the eye bolts. Angle them slightly toward the center of the swing to minimize the torque on the pipe and prevent the bolts from breaking.

Note: During the final assembly, squirt thread-locking compound on the eye bolt threads. Cut the eye bolts flush with the nuts and add rubber caps to the pipe ends for safety.

Attach the six seat slats (N) to the seat braces (Al and A2) by predrilling and screwing them into place with 1 %-in. deck screws. Use α countersink bit to ensure the heads are sunk below the seating surface. Attach the seat slat at the base of the seat tight against the back slats (H and J). Space the remaining slats so the gaps between them are even (around $\frac{1}{4}$ in.) and the front seat slat overhangs the front stringer (C) by ½ in. Note: A few slats may touch due to the shape of the

INSTALL SEAT SLATS

PEVEN OUT HIGH SPOTS
Because the seat curves, the slat edges can ride high in some areas, making for an uncomfortable ride. Smooth any high spots in the seat slats

seat—see Figure B.

with an orbital sander. Then sand the entire swing with 150-grit sandpaper.

The swing is now ready for any exterior stain, paint or finish (we used a semitransparent exterior stain). Wipe off the dust and vacuum the swing, then use a brush or roller to apply.

Hang the swing securely using special quick-link eyes to join the lengths of chain. The swing should tip back slightly at the arms, about 1 in. from back to front, when at rest.

INSTALL THE SWING

Screw a length of treated 2×4 into solid framing to support each chain. Be sure to use 4-in.-long lag screws and span at least three ceiling joists on your porch.





Mow your Zoysia lawn once a month – or less! It rewards you with weed-free beauty all summer long.

Ways Our Amazoy Zoysia Lawn Saves You Time, Work and Money!

CUTS WATER BILLS AND MOWING BY AS MUCH AS 2/3

Would you believe a lawn could look perfect when watered just once? In Iowa, the state's biggest Men's Garden club picked a Zoysia lawn as "top lawn—nearly perfect." Yet, this lawn had been watered only once all summer!

Plant Amazoy in an old lawn or bare ground. Set plugs into holes in the soil checkerboard style. Plugs spread to create a lush, thick lawn, driving out weeds. Easy instructions included with every order.

No weeding means no costly chemicals. Amazoy Zoysia lawns naturally resist insects, so you'll save money, while helping to protect the environment. Never expose your family and pets to weed killers and pesticide poison.

FOR SLOPES, PLAY AREAS, BARE SPOTS AND PARTIAL SHADE

Can't beat Amazoy as the low-cost answer for hard-to-cover spots, play-worn areas, partial shade and erosion on slopes.

Meyer Zoysia Grass was perfected by the U.S. Gov't, released in cooperation with the U.S. Golf Association as a superior grass.

IT STAYS GREEN IN SPITE OF HEAT AND DROUGHT

"The hotter it gets, the better it grows!" Amazoy Zoysia thrives in blistering heat, yet it won't winter-kill to 30° below zero. It goes off its green color after hard frosts, and begins regaining its green color as temperatures in the spring are consistently warm.





Your Assurance of Lawn SUCCESS Amazoy Zoysia Grass is GUARANTEED

Guaranteed to grow new green shoots within 45-60 days or we'll replace it **FREE** – for up to 1 year – just call us. Valid on one order at a time, typically the most recent. We ONLY ship you mature, hardy field grown genuine Amazoy Zoysia grass harvested direct from our farms. Easy planting and watering instructions are included with each order.

© 2024 Zoysia Farm Nurseries, 3617 Old Taneytown Rd, Taneytown, MD 21787

6 CHOKES OUT CRABGRASS AND WEEDS ALL SUMMER

Your established Zoysia lawn grows so thick, it simply stops crabgrass and most summer weeds from germinating!

NOW 3 WAYS TO START YOUR AMAZOY ZOYSIA LAWN!

1) Freestyle Plugs come in uncut sheets containing a maximum of 150–1" plugs that can be planted up to 1 ft. apart. Freestyle plugs allow you to make each plug bigger and plant further apart — less cutting and planting — you decide.

2) Precut Super Plugs come precut into individual 3"x3" plugs ready-to-plant (minimum 1 per 4 sq. ft.). They arrive in easy to handle trays of 15 Super Plugs. Save time and get your new lawn faster!

3) Amazoy Approved Seed – As The Zoysia Specialists for 70 years, we now have a Zoysia seed that meets our standards and homeowners expectations.

ORDER TODAY - GET UP TO 1,500 FREESTYLE PLUGS - FREE!

Freestyle Plugs You decide how big to cut the plugs. Each grass sheet can produce up to 150-1 in. plugs. Plant minimum 1 plug per sq. ft.

	Max Plugs	Free Plugs	Grass Sheets	Your PRICE	+Shipping	SAVINGS
8	450		3	\$ 47.50	\$26.50	<u> </u>
	750	+150	6	\$ 72.50	\$32.50	29%
	1100	+400	10	\$110.00	\$47.50	36%
	2000	+1000	20	\$185.00	\$75.00	47%
	3000	+1500	30	\$245.00	\$90.00	55%

Super Plugs Precut plugs 3 inches by 3 inches READY TO PLANT Packed in trays of 15 Super Plugs. Plant minimum 1 plug per 4 sq. ft.

Super Plugs	Free Plugs	Tray	Your PRICE	+Shipping	SAVINGS
15		1	\$ 27.50	\$18.00	
25	+5	2	\$ 42.50	\$25.00	26%
60	+15	5	\$ 97.50	\$37.50	41%
120	+30	10	\$150.00	\$60.00	54%
240	+60	20	\$270.00	\$97.50	60%

EVERYTHING YOU NEED TO START AND MAINTAIN A CAREFREE BEAUTIFUL ZOYSIA LAWN

Scan QR code to learn more

PLANTING TOOLS • PLANT FOOD • WEED AND PEST CONTROLS
ORGANIC PRODUCTS • SOIL TESTS • GARDEN GLOVES • EDGING and more!

www.ZoysiaFarms.com/mag or 410-756-2311

Harvested Daily from Our Farms and Shipped to You the Same Day the Plugs are Packed Amazoy is the Trademark Registered U.S. Patent Office for our Meyer Zoysia grass.

Savings shown over aggregate base price and shipping



Improving America's Lawns Since 1953

Use Promo Code 5233



SWAY YOUR WAY

WHETHER YOU BUILD IT OR BUY IT, A SWING CAN FIT YOUR PORCH—AND YOUR LIFESTYLE

BY CHRISTINE CAMPBELL

LOUNGE THE DAY AWAY

Keystone Amish Co. York Red Cedar Porch Swing Bed, \$1,540, theporchswingcompany.com

Increasingly popular across the South and in coastal areas, roomy daybed-style swings are often bedecked with a mattress-like cushion and pillows. Sturdy ropes enhance the coastal aesthetic, and in true southern summer style, the four-point installation offers

a relaxed sway more than a true swing.

Highlights: Comfortable, roomy, high

weight capacity

Drawbacks: Expensive, large





WICKER WONDERLAND

International Caravan Diamonds 4-ft. Resin Wicker Porch Swing, \$575, theporchswingcompany.com

Lightweight, stylish wicker can be made with a variety of materials—the term "wicker" simply refers to the weaving method itself. For an outdoor swing, opt for a synthetic material that won't weather in the sun or harbor moisture and mold. Pair with hanging planters, flower boxes, and colorful outdoor cushions for a boho-botanical feel.

Highlights: Lightweight, attractive

Drawbacks: Bulky profile, tricky to repair/clean

NO PORCH? NO PROBLEM

Arlmont & Co. Kemora Porch Swing with Canopy, \$340, wayfair.com

Standalone swings can be placed anywhere from a stone patio to the backyard. There are just as many styles as there are for your porch, and some models come loaded with accessories such as cup holders, reclining seats and awnings to keep you shielded from the elements.

Highlights: Easy to install, versatile, room for custom features

Drawbacks: Exposed to weather, no "built-in" look, large footprint



TOP RIGHT AND BOTTOM LEFT: VIA THE PORCHSWING COMPANY; BOTTOM RIGHT: VIA WAYFAIR FOR ARLMONT 8

ALL-NEW DIY BOOK FOR 2024

SAVE ON PRICEY SERVICE CALLS

by tackling home repairs yourself!

Your toilet is a leaky mess. Now what? You could call a plumber and pay to have it fixed, or you could do it yourself and SAVE! Allnew *Family Handyman Before*You Call a Pro will show you how!

You'll find the know-how, tools and techniques you need to **save hundreds of dollars** in common home repairs and improvements by doing them yourself, with professional-quality results.

WHAT'S INSIDE:

- 875+ Tips & Projects divided by the "pro" you'd call, addressing the most common issues around the entire house.
- Bonus Special Section filled with essential skills for preventing wear and damage that requires a pro.
- Detailed Photos & Illustrations, plus step-by-step directions, cutting guides & shopping lists.









CLAIM YOUR COPY TODAY!

ONLY \$10, including FREE SHIPPING, at

familyhandyman.com/B4C1



Scan & Order Online







hether it's breakfast as the sun rises or dessert under a blanket of stars, there's nothing like dining on your patio. Don't have a table to hold the potluck dishes, or chairs to place around the fire pit? Skip the store, save money and satisfy your appetite for a quick and easy DIY with these simple step-by-step projects.


Having woodworking skills certainly helps, but these builds are easy enough for even a beginning builder to hammer out in one weekend.

THE CHAIRS MATERIALS LIST (FOR ONE CHAIR) ITEM QTY. 1-lb. box 1¼" stainless steel screws FIGURE A EXPLODED VIEW 180-grit sandpaper 2" SCREW 1x3 x 8' cellular PVC boards OVERALL DIMENSIONS: Composite decking screws w/ plugs 1 box 351/4"T X 27"W X 331/4"D 2½" galvanized carriage bolts 4 1x4 x 8' cellular PVC boards 3½" galvanized carriage bolts 8 Galvanized nuts and washers PVC glue 2" SCREW 2" SCREW 1/4" X 31/2" CARRIAGE **WASHER BOLT** 1/4" NUT 11/4" 15° **SCREW CUTS** 15° 1/4" X 21/2" CUT CARRIAGE PRO TIP **BOLT** After all your hard work measuring the wood for the build, you'll want to make sure you have the properly sized cushions. We suggest: 4 in. thick, 21 in. wide and 44 in. long. 1/4" X 2" CARRIAGE BOLT 1/4" X 31/2" -CARRIAGE **BOLT** FIGURE B **CUTTING LIST** (FOR ONE CHAIR) MATERIAL LENGTH NAME 1x4 281/4" Seat sides Α (10-degree cut one end)* 211/2" 1x4 Seat front, back top 1x3 191/2" Seat supports (15-degree cut one end)* 1x3 271/2" D Back supports 21/2" (15-degree cut one end)* 241/2" Ε 1x4 Back sides (15-degree cut one end)* 231/2" 8 1x4 Legs 10° CUT (APPROX.) 193/4" 1x3 G Bottom back slat (cut to fit) (PART 73/4" Η 1x4 193/4" Slats, back brace (cut to fit) A) 1x4 291/4" Arms *Measure to long point on all angled parts









USING PVC

Cellular PVC is a great material for outdoor furniture. It will last forever without needing sanding or refinishing.

We recommend switching out your saw blades for specialized blades to cut composite or PVC material; you'll end up with smoother cuts. You can find the 1-in.-thick PVC boards we used at home centers. Mostly used for exterior trim, they have one smooth side and one grain side. That means you'll have left and right sides to Parts A, D and E.

For each of these pairs, make sure the angled cut goes one direction on one part and the

opposite direction on the other. This will allow you to assemble the chair with the grain side of the cellular PVC facing out.

PVC also requires special composite screws. They come with a special bit that sinks them just right into the material as well as plugs to hide the holes.

CUT THE PARTS

Making more than one chair means cutting a lot of pieces to the same length. A stop block lets you cut a bunch without measuring and marking each board. Using a miter saw, begin by cutting all the parts except G and H.

ASSEMBLE THE SEAT BASE

Screw the front to the sides using 2-in. composite decking screws, then PVC glue and screw the seat supports to the sides using shorter 11/4-in. stainless steel screws. If necessary, raise or lower the seat supports slightly so that the space above them matches the thickness of the seat slats.

BUILD UP THE BACK SUPPORTS

Screw and glue the back supports to the back sides. Position the back supports to match the thickness of the back slats.









BOLT ON THE BACK

Attach the back to the seat side with galvanized car-

side with galvanized carriage bolts. Then screw the back brace to the back side supports.

BUILD THE LEGS

Because PVC can be somewhat flimsy, we doubled up the legs for this chair. Take two of the leg parts (F) and glue the smooth sides together flush on all sides with PVC glue. Keep the parts flush with a few 1½-in. stainless steel screws.

7 ATTACH THE LEGS

On a flat and level workbench, clamp a pair of legs to the seat and back. The front legs should be clamped $2\frac{1}{2}$ in. from the front of the seat base and 11 in. from the bottom of the seat base to the bottom of the leg. The back legs should be close to $7\frac{3}{4}$ in. to the bottom of the leg and flush with the back angle of the seat base (A).

These measurements are approximate and will need adjustment if the legs are not


all flat on the floor. Check the legs for plumb and the seat for level, then bolt on the legs.

FASTEN THE SLATS


Place the slats on the seat and the back. Position the end slats first, then space out the slates between them evenly (typically 3/8 in. apart).

We started spacing the slats for the back from the top and left a slightly larger gap where the outdoor cushion will cover at the bottom. We used spacers to keep the









spacing consistent, then fastened the slats securely with a composite decking screw on each end.

MARK THE ARM NOTCH Place the arm on top of the legs and mark the angle where it meets the back of the seat. Transfer the mark to the top and bottom of the arm and mark a notch that matches the width of the seat back sides (E).

CUT THE NOTCH
Set the table saw fence
and cut the long side of

the notch first. Keep the top of the armrest facing up and stop when you reach the line at the end of the notch. To cut the rest of the notch, use a jigsaw or handsaw to match the angle traced in the previous step.

MOUNT THE ARMS Set the arms in place and screw them to the tops of the legs. After the chair is completely assembled, it's a good idea to take 180-grit sandpaper and ease all the corners. It's for your safety; the PVC

boards don't have rounded corners and can get a little sharp.

PLUG THE SCREW HOLES The last step is filling all the screw holes. The plugs feature the same grain pattern as the boards; to really help them blend in, be sure to line up the grain direction of the plug with that of the chair.

WHATIS AVAXHOME?

the biggest Internet portal, providing you various content: brand new books, trending movies, fresh magazines, hot games, recent software, latest music releases.

Unlimited satisfaction one low price
Cheap constant access to piping hot media
Protect your downloadings from Big brother
Safer, than torrent-trackers

18 years of seamless operation and our users' satisfaction

All languages
Brand new content
One site



We have everything for all of your needs. Just open https://avxlive.icu

THE TABLE

FIGURE A

OVERALL DIMENSIONS: 30"T X 66"W X 335%"D


CUT THE TABLE BASE PARTS

It's best to use a miter saw to cut all your parts, but a circular saw will be just fine if you're accurate with your cuts.

We set up a stop block on our miter saw to cut the legs, side and end aprons, and stretchers. With a stop block, you can make sure each part is cut to the same length.


CHOOSE THE BEST FACE Identify the most attractive sides of the cedar pieces. Look for imperfections as well as the tone of the wood so that it matches the other sides. Mark the "bad" side of the board, then drill two pocket holes on each end of the aprons (B and C) on this side.

While you're at it, drill pocket holes into the ends of the stretchers (E). One side gets one in the center, and the other gets two near the edges.



CUTTING LIST


	KEY	QTY.	DIMENSIONS	PART	
	Α	4	4×4 x 29"	Legs	
	В	2	2×4 x 26 ³ / ₄ "	End aprons	
	С	2	2×4 x 55"	Side aprons	
	D	4	2×4 x approx. 6%"(cut to fit)	Corner braces	
	Е	4	2×4 x 281/4"	Stretchers	
	F	6	1×5½" x 66"	Tabletop	










Take your outdoor cooking to the next level with Bacon Up® Bacon Grease. NOW AVAILABLE in the outdoor cooking section of select hardware stores nationwide!









PATIO TABLE LEGS

Arrange the aprons and legs with their good sides facing out on a large flat work surface. Position each apron ½ in. from the outside edge of the legs, then fasten them together using exterior washer head screws through the pocket holes. Fasten all four legs in this way to create the frame of the table.

SPACE OUT THE STRETCHERS

Flip the table to stand on its feet. Then space out the four stretchers (E) evenly, about 10% in. on center. Fasten them between the side aprons using exterior washer head screws.

Be sure the tops are flush with the side apron (C).

FASTEN CORNER BRACES

Using a few longer cedar 2×4 offcuts, cut a 45-degree angle on the ends, then cut the four corner braces (D) using a miter saw. The measurement from the long points of the cuts should be approximately 6% in. With the corner braces sitting tight against each apron, the brace should be just touching

the corner of the leg, but a small gap here will work fine.

Fasten each of the braces

in place with a pair of screws into each apron. Next, drill two 5/16-in. pilot holes through the

center of the brace and into the leg for the hanger bolts. Bore out the holes in the corner brace with a larger 7/16-in. drill bit.

REMOVE POCKET SCREWS

Fasten the aprons near the legs together with a piece of scrap 2×4, then remove the corner brace followed by the pocket screws securing the aprons to the leg. The leg is now detached from the table base.

Reattach the corner brace, slide the legs in place and tighten them on. Upon removing the pocket screws, the legs can be removed for easy transport as well as storage of the furniture during winter.














DRIVE IN THE HANGER BOLTS

With the corner brace reattached, slide a washer on the hanger bolt followed by two nuts. Keep the nuts toward the end of the bolt. Using two wrenches, tighten them together. When tightened together, they won't turn on the bolt. This lets you tighten the hanger bolt and drive it all the way into the table leg.

Once the hanger bolt is in place, loosen the bolts against each other. Remove one and tighten the other to secure the table leg.

BORE A HOLE FOR FEET Flip the table upside down. On the bottoms of the legs, draw two lines connecting opposite corners to form an X. This is the center of the leg. Then, with a $1\frac{1}{2}$ -in. Forstner bit, bore a hole in the bottom of each table leg about ¾ in. deep.

DRILL DEEP FOR ADJUSTABLE FEET

The feet we're installing are adjustable up to 1½ in. They're fastened with a T-nut into the $1\frac{1}{2}$ -in. hole we drilled in Step 8.

To make room for the adjustment bolt, drill a ½-in. hole 2 in. deep. Then place the adjustable foot's bolt into the hole and give it a light tap with a hammer to seat the T-nut.

OUTDOOR TABLETOP Flip the table upright and cut all the PVC deck boards 2 in. longer than the table base. Lay the boards on top of the base with a gap of around 1/16 in. between each. Make sure the overhang is consistent on the sides and the ends.

FASTEN THE TOP Use special composite deck fasteners made for PVC deck boards. We ordered

these screws along with the composite decking at a local lumberyard. The screws came with a special drill bit that sets the screws into the boards just right, along with matching plugs.

We used a Speed square lined up to the framing in the table base to help drive the screws in the same place and in a straight line over the width of the table. If you're building this table to be taken apart, don't drive screws into the tops of the table legs.

HIDE THE SCREW HOLES WITH PLUGS

The plugs for the decking material come with grain on the surface that matches the grain of the composite decking perfectly. Orient the plugs so the grain direction is continuous. Give them a few taps with a hammer to drive them flush with the tabletop. You're done!



PLANTER BOXES

3 1/4/5

THERE'S MORE THAN ONE WAY TO SHOW OFF YOUR GREENERY. HERE'S HOW TO CREATE PLANTERS FOR A RAILING, PATIO AND WINDOW.

lanters not only add a beautiful and vibrant element to your outdoor space but also provide a practical way to grow and display your favorite plants, herbs or flowers. Whether you have a small balcony or a spacious deck, there is a planter style for you.

BY FAMILY HANDYMAN EDITORS

WINDOWPLANTER

This stripped-down window planter can be built in less than an hour, and the simple design resists rot far better than traditional window boxes.

CUT BOARDS TO LENGTH AND MAKE HOLES

Cut the 1×10 and 1×3 boards to length (see Photo 1 and Photo 3 for dimensions). The precise diameters of 6-in. pots vary, so size the holes by scribing and cutting out a 6-in. circle from cardboard to ensure that the pot will rest on its rim (Photo 1). If needed, keep testing to find the proper size. Next, mark three 6-in.-dia. holes with a compass (use your adjusted measurement if applicable). Drill ½-in. starter holes and cut out the openings with a jigsaw.

CUT WOOD BRACKETS Mark the notch for the hang- \longrightarrow ing strip and both $1\frac{1}{4}$ -in. ends on the brackets. Make sure the grain runs parallel to the shelf for strength. Use a 5-gallon pail lid to scribe the bracket curves (Photo 2), then cut out the brackets with a jigsaw.

ASSEMBLE AND **MOUNT PLANTER**

Smooth off any rough edges and paint all the parts before assembly. Predrill and screw the hanging strip to the brackets. Then center and screw the shelf to the brackets and to the hanging strip.

Mount the shelf to the wall by screwing through the hanging strip into the wall framing.

MATERIALS LIST


(FOR ONE PLANTER)

ITEM	QTY.
1x10 x 3' board	1
1x3 x 3' board	1
2" exterior screws	
2x8 x 2' board	1
3" exterior screws	
6" clay pots	3

PRO TIP

Use colored clay pots to add some visual interest and boost your home's curb appeal.







WHAT IT TAKES

TIME COST \$100 <1 hour

SKILL LEVEL

Beginner

TOOLS REQUIRED

4-in-1 screwdriver, cordless drill, countersink drill bit, drill bit set, jigsaw, level, miter saw, compass, 5-gallon bucket lid (to use as template for brackets)



3-SEASON PATIO PLANTER

This project is lined with an ordinary plastic planter box—the kind you can get at any home or garden center. That means you can lift out one plastic box and drop in another, instantly swapping container plants.

PRO TIP

Start the growing season with spring bloomers in your planter while the other plants grow elsewhere. When the spring plants fade, you can pot the next set of plants.



CUTTING LIST

KEY	QTY.	DIMENSIONS	PART
Α	2	3/4" x 8" x 117/8"	Plywood ends
В	2	3/4" x 32" x 111/8"	Plywood sides
С	2	2¾" x 8" x 7¾"	Plywood braces
D	4	1" x 3" x 15"	Legs
E	4	1" x 2" x 15"	Legs
F	2	1½" x 3½" x 13½"	Beveled cap
G	2	1½" x 3½" x 36"	Beveled cap
Н	4	3/4" x 21/2" x 281/2"	Top trim (cut to fit)
J	4	3/4" x 21/2" x 6"	Trim (cut to fit)
K	22	5/8" x 31/4" x 67/8"	Lengths of beadboard

Overall dimensions: 36"L x 13½"D x 16½"T

MATERIALS LIST

ITEM	QTY.	
2' x 4' ¾" CDX plywood	1	
5/4x6 x 6' deck board	1	
2x4 x 6' cedar or pine board	2	
1x3 x 6' cedar or pine board	2	
5/8" x 31/2" beaded tongue-and-groove	14'	
Water-resistant glue		
4d, 8d and 12d galvanized casing nails		
6d galvanized box nails		
1¼" deck screws		
Plastic planter (to fit 61/2" x 29" opening)		

BUILD THE BOX Cut the plywood ends (A) and sides (B) to size and glue and nail the sides to the ends. Use clamps to hold the

ends upright.

ADD THE BRACES Center plywood braces (C) at each end of the planter. Predrill screw clearance holes through the planter sides and screw in the braces.

ASSEMBLE THE LEGS Rip 5/4-in. decking material und cut it to length for the legs. For each leg, glue and nail a 3-in. piece (D) to a 2-in. piece (E).

ATTACH THE LEGS Set the plywood box on a flat surface and screw the leg assemblies to it. Make sure the legs are flush with the top of the planter box.

BEVEL THE CAP BOARDS Rip a 20-degree bevel on the \bigcirc 2×4 caps with a table saw. Use a featherboard and push stick for extra safety.

ASSEMBLE THE CAP Cut the cap pieces (F and G) to length with 45-degree miters on the ends. Drill pilot holes for the nails. Then glue and nail the miters together.

7 ATTACH THE CAP Drill pilot holes and glue and nail the cap to the planter, measuring to make sure the overhang is even on all sides.

COVER THE BOX Cut the trim pieces (H and J) to length and nail them to the top and bottom edges of the box with 4d galvanized casing nails. Cut the beadboard (K) to fit and glue the pieces onto the plywood with construction adhesive. Let dry.





GALVANIZED

CASING

NAILS







11/4"

DECK

SCREWS





RAILING PLANTER

Got leftover wood? Try this compact project. It takes about a day to build and you don't need a lot of woodworking skills to give it a try.





Following the measurements specified in the Cutting List, use a miter saw to cut the two long sides (A) from 1×10 material. Then cut the two short sides (B) and the planter bottom (C) from 1×6 material.

CUTTING LIST

KE	QTY.	DIMENSIONS	PART
Α	2	34" x 91/4" x 36"	Long sides
В	2	34" x 5½" x 7%"	Short sides
С	1	34" x 5½" x 34½"	Bottom
D	8	3/4" x 11/2" x 371/2"	Long slats**
Ε	8	3/4" x 11/2" x 81/2"	Short slats**

**Mitered ends; cut to fit.

Overall dimensions: 37½"L x 8½"W x 9¼"T

MATERIALS LIST

ITEM	QTY.
1x10 x 8' cedar board	1
1x6 x 8' cedar board	1
1x2 x 8' cedar board	5
1¼" 18-gauge nails	
2" 18-gauge nails	
Exterior polyurethane	

ASSEMBLE THE BOX

With 2-in. nails to secure the bottom edge of the short sides (B) flush to the bottom face of the box bottom (C). Next, nail the long sides (A) onto the U-shaped short side/bottom configuration so that the top edge is flush with the top of the short sides (B) and there is 13/8 in. of the long sides (A) extending past the bottom (C).

WHAT IT TAKES

TIME COST <\$100

SKILL LEVEL Intermediate

TOOLS REQUIRED


Miter or circular saw, 18-gauge nail gun, drill/driver, 3/8-in. drill bit, clamps, Speed square, tape measure, foam brush


CUT THE SLATS


Cut the long (D) and short slats (E) from 1×2 material with a 45-degree miter on each end. Be sure to measure and cut these pieces carefully so that the distance between the miters precisely equals the box dimensions.


ATTACH THE SLATS

Attach the long (D) and short slats (E) to the planter with an 18-gauge nail gun and 1½-in. nails. You may find it easier to put all the slats on a single side of the box at a time, but you can also attach them ring by ring. However you attach them, ensure they are evenly spaced, leaving a 5/8-in. gap between the slats. Use clamps to hold the slats in place while laying them out and nailing.














DRILL DRAINAGE HOLES Use a drill with a 3/8-in. drill bit to drill three drainage holes in the bottom of the planter.

APPLY POLYURETHANE With a foam brush, apply two coats of exterior polyurethane to the planter. Allow appropriate drying time (read the manufacturer's directions) before using the planter.

TOTAL SET OF STATE O

Elevating the planter box slightly off the railing is essential. This ensures that the deck railing and planter bottom do not rot out. You can use pebbles or composite shims for this task, but we opted for plastic feet. They are often advertised as cutting board or furniture feet and are usually $\frac{1}{4}$ -in. or $\frac{3}{8}$ -in. tall. Move your planter after each watering or rainfall to further protect your railing.










We've lowered the prices on many of the essentials woodworkers need. Look for our New Everyday Value items storewide.

HELPING YOU MAKE WOOD WORK®

To Find Your Local Woodcraft Store, Visit woodcraft.com or Call 800-225-1153.







OUTDOOR/LAWN & GARDEN

Mow up to 5 acres with the DR® ZT5e electric zero-turn mower. This commercial style mower features DR®'s unique battery platform that allows you to customize the power source to the size of your property! Learn more at DRpower.com

Want a great lawn? Start with a better grass – Amazoy Zoysia Grass! Learn more: 1.410.756.2311 | Zoysiafarms.com

TOOLS

Since 1928, Woodcraft has been outfitting woodworkers and their shops with everything woodworkers want. Find the best tools or the most amazing wood for your next project.

Woodcraft.com/catalog

Grizzly Industrial, Inc. Purveyors of Fine Machinery since 1983. 1.800.523.4777 | Grizzly.com

Superior Quality Sliding, Folding and Pocket Door Hardware. Made in the USA since 1958.

1-574-293-5664 | Johnsonhardware.com

Get every project done in comfort with our composite safety toe boots that feature Goodyear® slip-resistance, EH protection and Arch Fit® support.





















skechers.com





GATHER AROUND AS PRO BRICKLAYER DOUG MONTZKA SHARES HIS TIPS FOR BUILDING A LASTING OUTDOOR **GATHERING SPOT**



PLAN AHEAD

This project needs to be spread out over a few days. First, you'll have to pour the footing and give it time to set. Then you'll have to mortar the bricks into place.

Before digging out the space for your fire pit, call your utility companies (dial 811; for more info, go to call811.com) to check the location of buried utility lines.

Also check the fire pit code in your area. Most require a fire pit to be 25 ft. away from any structures and overhanging trees. And think about how the prevailing winds affect your space.

WHAT IT TAKES

TIME	COST	SKILL LEVEL
Multiple	\$400	Intermediate
days	20	

TOOLS

Brick hammer, bucket, concave jointer, concrete float, cordless drill, level, margin trowel, mason's trowel, safety glasses, shovel, tuck-pointing tool, wheelbarrow, hand tamper, sledgehammer

MATERIALS LIST

ITEM	QTY.
Face bricks	120
Firebricks	25
36" cardboard concrete form	1
48" cardboard concrete form	1
4x8 hardboard sheet (if making own form	s) 1
Type N mortar mix, 80-lb. bags	5
Refractory cement (sold at brickyards)	½ gal.
Concrete mix, 80-lb. bags	10
3/8" rebar, 10' lengths w/ ties	2
Spray paint	1 can

MARK OUT THE FIRE PIT

First, choose a spot in your yard for the fire pit base. A 3-ft.-dia. pit creates enough room for a good fire, yet keeps everyone close enough to chat (and complies with most codes).

To make your own forms, rip α 4 x 8-ft. sheet of 1/8-in. hardboard into four 8-in.-wide strips. Carefully bend and screw two strips together to create a 36-in.dia. circle, and use the other two

PRO TIP

To make measuring the pit and pouring the concrete footing easier, use two cardboard concrete form tubes (purchased from a concrete supply company).

to make a 48-in.-dia. circle. Set the larger form in position and spray paint around it.

O DIG AND LEVEL THE HOLE Following the painted guide, L shovel out the soil to α depth of 8 in. for your fire pit base. Do not disturb the underlying soil.

Check the bottom of the hole with a level and remove any high spots by scraping off soil rather than digging. This leaves the underlying soil intact.


Compact the soil with a hand tamper or a 4×4 post.

STAKE THE FORMS

A concrete footing will create a stable base for the pit walls and keep the sides of your pit from cracking as the ground moves over time.









Stake the forms and mix up ten 80-lb. bags of concrete mix per manufacturer directions.

If you're using hardboard forms, stake them so they're nice and round.

If the forms aren't quite level, raise one end and drive a screw through the stake.

ADD THE REBAR

Bend the two rebar lengths to form a 42-in.-dia. circle. Bind the overlapping ends with wire to form a sturdy ring.

Fill the forms halfway, then press the ring into the concrete for strength. Make sure it doesn't touch the sides of the forms.

FINISH THE FOOTING Shovel in the remaining concrete until the forms are

filled to the top and then tap the forms gently with a sledgehammer until the concrete mix is level.

Recheck the level, hammering the forms down if necessary, and smooth the top of the footing.

Let the concrete completely set up overnight. Remove the forms the next day.

DRY-SET THE FIREBRICK LINER

Regular clay brick can crack at high temperatures, so we're using firebrick (also called refractory brick) to line the inside of the fire pit walls. You will need 25 firebricks for a 3-ft.-dia. pit.

Because firebrick is so dense, it's tougher to split than regular brick. "Soldiering" the brick

PRO TIP

Firebrick is kilned to withstand high temperatures. It's larger, thicker and wider than regular brick, and you can find it at most brickyards.

(standing it on end) minimizes splitting and lets you easily accommodate the pit's curve.

For this project, you'll only need to split four firebricks, which you'll place across from one another around the pit to create draw holes for oxygen for your fire (see Step 8).

Dry-set the firebricks in place on top of the footing. Space out the bricks so that you won't have to cut the last brick to fit.

Mark the position of every brick on the footing.









Firebrick is mortared with refractory cement, which can withstand high heat. It comes premixed in a bucket and has the consistency of peanut butter.

Butter a thin layer of cement on the footer (like you're spreading peanut butter on toast) and position your first brick.

Butter the second brick and butt it tightly against the first.

Continue around the circle, checking the level side to side and back to front as you go. Leave brick-sized gaps in four opposite points around the ring.

PRO TIP

A margin trowel makes it easier to scoop cement out of the bucket and butter the bricks. And a tuck-pointer is useful for cleaning up the joints.

Fill the open gaps with half bricks. These gaps are draw holes that feed air to the fire. Prop up the half bricks until the mortar sets.

Check the level across the fire pit and the vertical level of the bricks as you go.

DRY-SET THE FACE BRICK We used SW (severe weathering) face brick (also called common or building brick) to line the fire pit's outside walls. If your climate doesn't include freeze/thaw cycles, you can use MW (moderate weathering) building brick. You'll need 80 face bricks for a 3-ft.-dia. pit. Face brick with holes (cored) is easy to split with a brick hammer. It's easier to form the curve of the pit walls with half bricks. You'll lay three courses of face brick and mortar them together with Type N mortar mix.

Because face brick is smaller

PRO TIP

While our mason doesn't use gloves, we suggest you do!

than firebrick, you'll need to make up the size difference as you lay your three courses of face brick. The difference between the height of your firebrick and the total height of three stacked face bricks will determine the width of your mortar beds between courses.

Dry-set the face brick, marking where each course of face brick has to hit the firebrick to make the third course of face brick level with the firebrick.

SPLIT FACE BRICKS
Hold one face brick in
your hand, keeping your
fingers below the top edge of the
brick. Give the brick a solid tap
on the outside edge near the center hole. Avoid hitting your hand.
Repeat with the remaining 79
face bricks for the outside wall.





LAY A MORTAR BED To keep your mortar joints between courses a reasonable width, lay a 2-to-3-in.-thick bed of mortar right on top of the footing.

Let it set up slightly (give it at least 15 minutes) and smooth out the top.

WORK IN SECTIONS Working on one-third of the fire pit at a time, lay 3/8 in. fresh mortar on each course of face brick into place, leaving a $\frac{1}{4}$ -in. gap between the firebrick and the face brick.

Check the level of each course and tap down the bricks as necessary.

Stagger the joints between courses for strength.

CHOOSE THE RIGHT FIREWOOD

Using the correct firewood for your fire pit will make the experience more enjoyable for the person maintaining the fire as well as those sitting around it. Choose a wood that's easy to ignite and burns as cleanly as possible. This often comes down to the wood's density and moisture levels.

In general, hardwoods are denser than softwoods, and they dry more easily. That means they will create a low-maintenance, steady fire that lasts for hours. Softwood is easier to light and usually more affordable, but it will burn quickly, so you'll need to buy more wood and tend to it more often.

THE BEST TYPES OF WOOD TO BURN IN YOUR FIRE PIT

Bradley Hite, owner of Nashville Firewood, and other experts recommend the following wood types for their ease of lighting, limited smoke production and low cost.



Ash: Good for a steady, long-lasting fire; easy to find; affordable; clean-burning




Pine: Inexpensive, easy to split, crackles when burned to add ambiance (quickburning, so works best as kindling)



Oak: Easy to find, easy to split; burns long and slow if properly dried out; moderate smoke

THE WORST TYPES OF WOOD TO BURN IN YOUR FIRE PIT


Not all kinds of wood are safe to burn in a fire pit. Often, wood that you find at your campsite or around your home will light or burn poorly, produce excess smoke, or even be dangerous to your health.



Green (freshly cut) wood: Nearly impossible to light and burn steadily (hasn't had time to season or dry out)



Driftwood: Won't burn well if wet, especially if from the ocean; can create potentially hazardous toxins



Construction wood: Often treated with chemicals; may contain nails, glue and other finishes that pose additional risks

MACKENZIE EDWARDS

CLEAN A DIRTY FIRE PIT

If you already have a fire pit in your yard, chances are you've never thoroughly cleaned it. While you certainly aren't alone, routine cleanings are an important safety measure.


Tim Jankowski, president of Aladdin's Cleaning and Restoration in Lapeer, Michigan, who is an expert in fire prevention, says dirty fire pits harbor flammable debris that can build up over time. He suggests cleaning yours in the spring and again in the fall.

Before you start, make sure the fire has been out for at least a day. When it comes to cleaning products, Jankowski says, "dishwashing liquid is actually one of the best solvents" for tackling this job. For a brick or stone fire pit or fireplace, use a good strong bristle brush and follow up with a wet-dry vacuum to remove the debris and soapy water.

If you have have a cast-iron fire pit or any other metal fire pit, in-ground or portable, follow this technique:

- 1. Remove leaves and ashes. Put on rubber or work gloves to protect your hands. Brush or sweep out leaves and bits of wood and sticks. Use a shovel to scoop out ashes. Compost or otherwise discard leaves and ashes.
- 2. **Fill a bucket.** Squirt some dish soap in your bucket. Fill bucket with hot water.
- 3. **Scrub.** Dunk a steel wool or stiff brush in soapy water. Scrub the inside of the fire pit to remove rust, dirt and soot. Scrub the cooking grate with a scouring cleanser such as Bar Keepers Friend.
- 4. **Rinse and dry.** Rinse fire pit with garden hose. Wipe down thoroughly to prevent rust.

ALLY CHILDRESS







STRIKE THE JOINTS
After you finish each section of face brick, use a jointer to smooth (strike or tool) the joints before the mortar dries too much.

Striking gives the wall a uniform, polished look; the mortar is ready to strike if you press your finger into it and the indentation remains.

Remember to leave the draft holes open as you mortar each section of face brick and smooth out the finished joints.

FINISH THE TOP LIP

Mortar the brick caps.
Finish the pit with a matching "row-lock" cap using regular face brick set on edge (see page 49 for the final look).

You'll need about 40 face bricks for this cap, which will protect the wall joints from rain, contain sparks and give you a nice ledge to warm your feet on.

Working with 10 to 12 bricks at a time, lay a \(^3\)-in. bed of mortar and lay the bricks on edge, then butter each brick on the outside edge as you go and press it into place.

FILL GAPS
Add a small amount of mortar to the joints to fill any gaps.

Check the level frequently and tap gently with a brick hammer to adjust the spacing.

Leave a 1-in. overhang on the outside to allow rain to drip off.

Once all the bricks have been mortared in place, strike the joints with a concave jointer.

Give the cement and mortar a week to cure completely before lighting a fire in your pit.

Pour a few inches of gravel on the pit's floor for drainage, and you're ready for a wienie roast. Style Your Solo Stove

THEY'RE HOT, AND THEY'RE HERE TO STAY. **HERE'S HOW TO CREATE** THE PERFECT BACKYARD **SCENE WITH THIS** SMOKELESS FIRE.

BY NINA BRICKO

or a bonfire with benefits, look to the Solo Stove. This popular portable fire pit doesn't produce smoke, which makes it great for a backyard gathering. Follow these tips to wow your guests and make your night a flame-crackling success.


CHOOSE A SPOT

Put your fire by your garden for a romantic evening, or place it on the patio when hosting a party. Remember: It's portable! Interior designer Stephanie Fitch suggests keeping the Solo Stove in your everyday flow; if the pit is on your patio, close to doors, or visible from a window, you'll be more likely to use it.

KEEP YOUR DISTANCE

Be sure to check city codes to see how far away a wood-burning stove needs to be from your house. Avoid areas with low ceilings or overhead branches, and if you're placing the pit on a deck or in the grass, use a Solo Stove stand.

The stove's double walls, which help to manage smoke output, can become extremely hot, posing a potential risk to kids and pets. One option, suggested by landscape designer Joe Pendergast of LandWorks Landscape Services, is to install a traditional stone fire ring to keep small hands at bay. Solo Stove also sells Surround, a table and enclosure that is heat resistant and can hold your drinks.



LIGHTING

Outdoor all-weather string lights are not only pretty but also save you from having to turn on floodlights and ruin the atmosphere of the fire. For safety's sake, don't hang them directly above the stove.

MAKE IT COZIER

Small offerings of hospitality, such as a waterproof bin filled with outdoor blankets or family games, turn a regular fire into a party. Landscape architect Chris Miracle of LandWorks suggests using a wheelbarrow filled with ice as an easy way to deliver drinks to your guests. Also consider using stackable trays for snacks and s'more accoutrements.

PULL UP A SEAT

Chairs that are comfy and surround the fire are also essential. Their orientation won't matter, since

smoke isn't blowing in faces and disrupting conversation. However, Fitch says that using stumps or benches that can be pulled up for more seating is a must, especially if you want all guests to feel included—not just the ones who arrived early.

LIGHT YOUR FIRE

For starting a fire, Solo Stove recommends the "log cabin" method: Place small pieces of wood (about 8 x 1 in.) parallel to each other and 4 in. apart. Take two more pieces and stack them perpendicularly on top. Keep stacking until you have four to five layers and what appears to be a log cabin. Place a fire starter in the middle of the structure, and light it.

Once the fire has gone and there's only embers left, put the lid on to help it cool down completely. If you need a faster solution, never use water to put out fire from a Solo Stove; instead, use sand.

BEST PRO TIPS

EXPERT ADVICE FROM THE JOB SITE



ents to design harmonious spaces for both hound and human. His book *Petscaping: Training and Landscaping with Your Pet in Mind*, co-authored with animal trainer Carolyn Doherty, helps homeowners do the same. Here are Cohen's

top tips for getting started.

MEET THE PRO

SCOTT COHEN IS PRESIDENT OF THE GREEN SCENE LANDSCAPING AND POOLS IN CHATSWORTH, CALIFORNIA.

CHOOSE RUFF-AND-TUMBLE TURF


If your pooch puts your lawn through its paces, consider a traffic-tolerant grass that thrives under your site conditions. Among Cohen's preferred options for pets are hybrid Bermuda and zoysia (warm-season grasses), and tall fescue and Kentucky bluegrass (cool-season grasses). Another option is to establish a dedicated dog run with sand, pea gravel or artificial turf. Monitor your property's sun exposure throughout the day before selecting a location—"the hot, sunny side of the house is probably not the best place for a dog, especially in the summer months," Cohen says.

When it comes to those dreaded pee spots, one foolproof option is laying down artificial turf in a trained relief zone. But if your dog roams freely, watering affected areas right after your dog urinates helps dilute the excess nitrogen and salt before it can settle in the grass's root zone.



TREAT YOUR PETS LIKE FAMILY

Petscaping allows you to dream up new ways for you and your pet to enjoy the outdoors together. Cohen worked with one client to design a side yard for their family bull mastiff, Broamy. The project, cheekily titled "A Homey for Broamy," involved establishing a sand dog run outfitted with agility obstacles—and a dog bone-shaped bench for less-agile humans. If your dog prefers to lounge, consider a raised bed that keeps them off a hot deck or patio surface. Some options come with awnings. Other worthy upgrades include outdoor grooming stations, custom dog houses and even decorative fire hydrants. It's a dog's life, after all. "If there's any truth to reincarnation," Cohen says. "I'd like to come back as a dog."



WORK WITH YOUR PETS, NOT AGAINST THEM

Certain behaviors are core to your dog's identity: terriers dig, retrievers swim. "You don't want to create an environment that counters what they naturally want to do," Cohen says, as this can lead to even more behavioral problems. Instead, strike a balance between their needs and yours.


If your pooch loves to dig, for example, choose a shady spot you can easily monitor

and set up a dig pit. This might be a sand-filled kiddie pool or a hardscape feature lined with landscaping fabric and bordered with pavers. The key is to provide a visual border that shows your dog the "dig here" zone. Next, hide treats or toys under the top layer of sand and encourage your dog to root them out. They'll soon learn to contain their digging and you won't trip unexpectedly en route to the shed.

To address grass wear from constant fence line patrolling, consider

a brick- or flagstone-lined path that will look more finished and be easier to maintain. (If you opt for a mulched path, avoid cocoa bean mulch, which is toxic to dogs.)

And for water-loving pups with pool access, Cohen says, "you have to make sure there's an entry-exit point that allows the pet to get out of the water safely." Particularly poor swimmers, such as pugs and bulldogs, may benefit from the added safety of a fully fenced-off pool area. 🛍



PLANT WISELY (AND SAFELY)

While many common backyard plants will cause only mild digestive upset if your pet takes a bite, some, like sago palms and wisteria vines, can cause more serious side effects, particularly in puppies. If you're working with a landscaper, be sure to raise any concerns in your initial consultation. You can also check aspca.org for a detailed list of toxic plants.

Once you've narrowed down your options, line garden borders with grasses, ground covers and shrubs, which can withstand more abuse than delicate flowers and plants that have large, damage-prone leaves. If you do want to grow flowers or veggies, consider raised beds or containers. And when it comes time to fertilize or treat for pests, be sure to heed any package warnings and store the chemicals well out of your pup's reach.





HOME CARE MAINTENANCE & REPAIR | STORAGE & ORGANIZATION | HEALTH

OPERATION: ORGANIZATION

REAL-LIFE IDEAS FOR CLEVER AND PRACTICAL STORAGE SOLUTIONS THROUGHOUT YOUR HOUSE

BY NINA BRICKO

hether you have a tiny apartment or an enormous house, finding a spot for everything can be a challenge. And purchasing all the premade solutions you can find at a store can be overwhelming—and costly. The good news is that there are lots of little hacks you can do with leftover materials you might already have at your house. Have some PVC? Let's make curling iron holsters. Old closet rod? Create handy clothing storage in your laundry room. These simple solutions and easy builds will help you minimize clutter and make what you need more accessible.

BATHROM


My bathroom tends to be a travesty, with damp towels on the floor, curling iron cords dangling and just waiting to be stepped on, crumpled tissues strewn about and allconsuming bath toys. These ideas helped me change things.





SWINGING TRASH

The trash can is never in a good spot and, well ... it's ugly. Plus, it takes up precious floor space or is tucked oddly next to the toilet—gross. Under the sink and attached to the door, it's accessible and leaves some under-the-sink room for more storage! Screw wire shelf anchor clips to the inside of the door and hook the lip of a small wastebasket right on the hooks. Done and done.



TOOTHBRUSH MOUNT

Toothbrushes take up a lot of counter space. Here's a clever storage idea: Make a holder for them using large grip-type clips. Mount the clips on your medicine cabinet or on a piece of wood that you can hang on the wall. The clips work great to keep your toothbrushes secure! Now, if only we could get the kids to hang their wet towels.



PVC CURLING IRON HOLSTERS

First, you'll need to get those curling iron cords off the floor and wrapped up neatly. Then use hook-and-loop tape to attach 5-in. lengths of 2-in.-dia. PVC pipe to the vanity door to hold the barrels. Repeat with 3-in. pieces of $1\frac{1}{2}$ -in.-dia. pipe to hold the cords. Just measure your curling irons to see how long your "holsters" need to be.

KITCHEN

My husband has uttered a few unsavory words in our kitchen as he pulled out piles of bowls and dishes to find the one small thing he needed. Use these tips to get your space organized enough for anyone to roll in, grab what they need and get cooking.








Cutting boards are often too long or too clunky to fit on shelves or in cabinets, so where are you supposed to store them? I nearly squealed with joy when I found this hack. Essentially, you are mounting a cutting board rack on a cabinet door. Use a sheet of ¼-in.-thick acrylic plastic; plywood would also work. Cut the acrylic with a table saw or circular saw (be sure to cut slowly). Knock off the sharp edges with sandpaper and round the lower corners with a belt sander. Affix the acrylic to the cabinet door with four screws and finish washers; No. 14-8 crimp sleeves (sold in the electrical aisle at home centers) make good spacers, but any type of tube or even blocks of wood would work.



MOLDING TO HANG WINE GLASES

Stemware doesn't sit well in a cabinet. Using T-molding designed for wood floor transitions, I've made the perfect rack for stemware. Just cut it to length, predrill screw holes and screw it to the underside of a shelf. For a neater look, use brass screws and finish washers. Prefinished T-molding is available wherever wood flooring is sold.



CABINET DOOR KNIFE RACK

Sharp knives hanging about with your other cutlery just waiting to cause an accident? Use your cabinet door. (The higher the better if there are kids in the house.) To build this cutting board turned knife rack, you just need a table saw and wood scraps. Run the scraps across the saw on edge to cut kerfs. Adjust the blade height to suit the width of the knife blades. You have to remove the saw's blade guard for these cuts, so be extra careful. Also cut a thin strip to act as an end cap. Glue and clamp the kerfed scraps together and sand the knife rack until the joints are flush. To mount it, use two $1\frac{1}{4}$ -in. screws and finish washers.




ALL-NEW DIY BOOK FOR 2024

YEAR'S BEST

DIY TIPS, REPAIRS & PROJECTS!

Getting ready to fix up the house? Save time and money on all your plans with **The Best of Family Handyman 2024!**

You'll find idea-packed chapters loaded with expert advice on repairs, projects and upgrades for your entire home. Save hundreds of dollars in home improvements by doing them yourself!



WHAT'S INSIDE:

- √ 550+ Tips & Projects that solve common household problems while building value in your home.
- ✓ Bonus Special Sections filled with practical, no-nonsense advice every homeowner needs.
- ✓ Detailed Photos & Illustrations, plus step-by-step directions, cutting guides and shopping lists.



Scan & Order Online

CLAIM YOUR COPY TODAY! ONLY \$10, including **FREE SHIPPING**, at familyhandyman.com/2401F

STAY SAFE IN THE HOME YOU LOVE



Trustpilot

DID YOU KNOW?

- 1 in 4 seniors will fall this year.*
- Most falls happen on the stairs.
- Acorn Stairlifts has the best solution to stay safe on the stairs.

GET \$250 OFF**

YOUR PURCHASE OF AN

- A FREE STAIRLIFT BUYING GUIDE
- YOUR FREE INFO KIT & DVD
- ANSWERS TO ANY QUESTIONS YOU MAY HAVE

1-866-234-2906

PEDIAFISH

Ultra-fast.

Easy to Use.

*According to the CDC. **Not valid on previous purchases. Not valid with any other offers or discounts. Not valid on refurbished models. Only valid towards purchase of a NEW Acorn Stairlift directly from the manufacturer. \$250 discount will be applied to new orders. Please mention this ad when calling. AZ ROC 278722, CA 942619, MN LC670698, OK 50110, OR CCB 198506, RI 88, WA ACORNSI8940B, WV WV049654, MA HIC169936, NJ 13VH07752300, PA PA101967, CTELV 0425003 R5, AK 134057 HIC.0656293.





A complete pressure washing system from Generac that provides up to 3200 PSI and ALL the tools you need for fast, thorough cleaning!



PowerDial™ Gun puts pressure control at your fingertips!



Power Broom cleans decks and driveways up to 4X faster!



Cleaning Tools make washing anything fast and easy!

OFFER!*

Get the complete system with

Free Cleaning Tools & Free Shipping!

GeneracSpeedWash.com



ORDER TODAY!

*Visit online for offer details.



HOME CARE

KITCHEN TIPS (CONTINUED)



SHELF SMARTS

Small plates go on big plates, and then bowls go on the top. This is how my cabinet is organized. It's fine until you need a small plate. Most cabinets just have one or two shelves. But wait! Why not add another shelf—why not two? All it takes is ¾-in. plywood and a bag of shelf supports. I wish I would have thought of it sooner.

Note: The supports come in two diameters, so take an existing one to the store to make sure you get the right size.



MEASURING CUP STORAGE RACK

Make sure you can always find those pesky measuring cups and spoons. Hang them on a cabinet door. Position and mount a wood strip so that the cups will hang between the shelves and allow the door to close completely. Mount a second strip for your measuring spoons, then screw in cup hooks on both strips.

LAUNDRY ROOM

The dreaded laundry room with its soaps, baskets and iron. The cabinet above the washer and dryer is too high for a shorty like myself, so I tend to leave the necessities on top of the machines, which can be a problem when doing multiple loads. What I need is a simple solution that I can reach.



CLOSET ROD AND SHELF COMBO

The obvious solution is to add a shelf that you can reach with or without a stool, but if you are going that route, you might as well purchase shelf brackets that include a hook for a clothing rod. Now you can hang up your shirts and jackets as soon as they're out of the dryer—no more wrinkled shirts at the bottom of the laundry basket.



HIDDEN SHELVES

A cabinet above the washer is fine to store things for later, but what most shorties need is a shelf that's accessible. When you've got a small laundry room, it can be challenging. That's why a set of shallow shelves behind a door is the perfect remedy. This space is often overlooked and is just aching to be used. Just make sure to screw the shelves into studs and put a rubber bumper on the frame to protect the door. Voila! fh



World's Best Bed! Eliminates dressers, box spring, wobbly bed frame & dust. Fits in very small rooms. Top quality materials. You custom design your bed from 30 options. Ready to ship UPS in two days. It's a complete bedroom suite in one piece, plus, we also make the world's most comfortable mattress.

Solid wood, ball-bearing slides, 1000 Lb. Cap. 50 Yr. Warranty

Call: 800 851-9213

www.ultimatebed.com



The NEW sub-compact, easy to use **MAGNATRAC® RT1150**, is the perfect solution for homeowners that need to tackle all those tough jobs! Landscape your property, plow snow, skid logs for firewood, make gardens, make food plots and trails...even dig a small pond!



SAVE MONEY! Stop paying others to do jobs you could easily do yourself.



EASY TO USE! No shifting gears, just instant power to forward and reverse.



MADE IN THE USA! Quality craftsmanship, by American workers!



Get Your FREE Info Kit!

1-262-235-5722
Mention Promo Code: FHM424



STOP CLOGGED WET/DRY VAC FILTERS



STOPS

UP TO 99.9% OF DUST FROM REACHING YOUR WET/DRY VACUUM

See How It Works!



Ideal for use with:

- wood dust
- drywall dust
- water
- pet hair
- concrete dust
- and much more!

AVAILABLE AT SELECT



Durt Deputy
LOW-PRO PLUS







handyman

EDITORIAL

Chief Content Officer Content Director **Deputy Editor** Creative Director Associate Creative Director **Art Director** Deputy Editor, Copy Desk Copy Editor Senior Print Publication Designer Photographers

Jason Buhrmester Kirsten Schrader Kelly Aiglon **Christine Campbell** Raeann Thompson Kristen Stecklein Anna Jo Beck Ann M. Walter Rayan Naqash Sanjeev Dhiman **Mark Derse Dan Roberts**

Senior Set Stylist Melissa Franco

DIGITAL

Chief Content Officer Deputy Editor, Contributors & Community Senior Editor Associate Assigning Editor Newsletter Editor Associate Editor Senior Editor, Projects Senior Project Editor Projects Editor/Builder Studio Projects Editor Senior Builder, Quality & Safety Contributing Copy Editor

Allison Bean Executive Editor Ryan Van Bibber Berit Thorkelson

> Harrison Kral Mary Flanagan Alex Shoemaker Rebecca Wright-Brown Ethan O'Donnell Carmen De La Paz Samuel Rosenmayer Nina Bricko Frank Tritschler Pat Borzi

BUSINESS

Lora Gier

EVP, Sales & Marketing VP, U.S. Licensing Head of East Coast Sales Head of Midwest/West Coast Sales Kim Krubeck Hinrichs West Coast Advertising Director Director, Sales Analytics & Operations New York, 646-518-4215

Pete Holfelder Jr. Cory Rotkel Isabella Carrado Gisele Myer

Classified & Small Display Ads Advertising Coordinator VP, Insights Lab Associate Director, Research

Midwest, 312-540-4824

Kari Nestor Liz Spitaleri **Monica Weiss** Isabella von der Linden **Kathy West** Jennifer Izzo Nancy Forman Selena Cohen **Babette Lazarus** Sebastian Rodriguez

TRUSTED MEDIA BRANDS

President & Chief Executive Officer President, Digital Chief Creative Officer Chief Financial Officer Chief Marketing Officer Chief People Officer Chief Product Officer SVP, SEO, Partnerships & Digital Performance SVP, General Counsel EVP, Global Content Operations VP, Associate General Counsel/ Chief Privacy Officer VP, Benefits & Compensation **Bonnie Kintzer**

Vince Errico **Beth Tomkiw** Kanuj Malhotra Michelle Korchinski-Ogden Jennifer Tyrrell **Emily Christner** Jen Keller

Mark Sirota **Christina Smith** Paul Gillow

Heather Schwartz

EDITORIAL OFFICE

1610 N. Second St., Suite 102, Milwaukee, WI 53212



DO YOU CRAVE MORE FAMILY HANDYMAN?

Get our best tips and hints sent to your inbox. Sign up at familyhandyman.com /newsletter

GOT A DIY QUESTION?

Finding the answers is easy at familyhandyman.com. Click on the three bars at the top left of the page and then search your topic to get expert step-by-step help with your projects.

GOT A HANDY HINT OR TIP FOR US?

To share your idea with us, submit a copy of your original contribution, including photos and/or sketches, by email to:

submissions@familyhandyman.com

Or mail to: Family Handyman, 1610 N. 2nd St., Suite 102, Milwaukee, WI 53212

Please include your name, mailing address and email address if you have one, and indicate to which department you are submitting. We reserve the right to publish your submission in any appropriate department, or elsewhere. Contributions will not be acknowledged or returned.

RIGHTS

By submitting material to us, you grant Home Service Publications, Inc., its parent company subsidiaries, affiliates, partners and licensees worldwide use of the material without time limitation, including the right to use your name and city/state/province in connection with any such use. We reserve the right to modify, reproduce and distribute your material in any medium (now or hereafter existing) and in any manner or appropriate place, including but not limited to magazines, promotional merchandise and marketing, and other related materials.

By submitting material to us, you represent and warrant that you have full authority to grant the rights set forth above and that your material will not, in whole or in part, infringe the intellectual property rights, rights of privacy or publicity, or any other rights of any third party.



You further represent and warrant that you have attained the legal age of majority in your state/province (18 in most states/provinces). If you're a minor under the law of your state/province, your parent or guardian must submit on your behalf.

CUSTOMER CARE

For subscriptions, payments, account info, renewals, gifts and other inquiries, email: customercare@familyhandyman.com or visit: familyhandyman.com/customercare

You can also write to: Family Handyman Customer Care, PO Box 6099, Harlan, IA 51593-1599

Single copies of past issues are available for purchase at our affiliate, shop.tasteofhome.com. The cost is the cover price (\$5.99) plus \$1 shipping and handling for each copy.

COMMENTS AND SUGGESTIONS

We welcome your ideas and opinions. Write to: The Editor, Family Handyman, 1610 N. 2nd St., Suite 102, Milwaukee, WI 53212. Email: feedback@familyhandyman.com

TO REQUEST PERMISSION TO REPRINT

If you'd like permission to reprint any material that appears in Family Handyman, please write to us with the nature of your request. Please include as much detail as possible relating to your intended use of the material and specify the issue date and page number (or URL, as applicable) where the material originally appeared. Please send an email to permissions@tmbi.com

FAMILY HANDYMAN® ISSN: 0014-7230, USPS: 515-930. Vol. 74, No. 2, 631st Edition. Published 7 times per year: March, April/ May, June, July/August, September, October/November, December/January/February by Home Service Publications, Inc., 1610 N. 2nd St., Suite 102, Milwaukee, WI 53212. We may also occasionally publish extra issues and special issues (which count as two in a subscription). Periodicals postage paid at Milwaukee, WI, and at additional mailing offices. POSTMASTER: Send address changes to customercare@familyhandyman.com, visit familyhandyman.com/customercare or write to Family Handyman Customer Care, PO Box 6099, Harlan, IA 51593-1599. **SUBSCRIPTIONS:** In the U.S.A., its territories and possessions, \$24 for one year (7 issues). For countries outside the U.S.A., subscriptions are \$28.97 per year in American currency. Canadian GST registration number R123771891. CPM agreement number 40065693. Printed in the U.S.A. Copyright ©2024 Home Service Publications, Inc. All rights reserved. Unauthorized reproduction, in any manner, is prohibited. Family Handyman, Handy Hints, Great Goofs and Build It. Fix It. Live It! are registered trademarks of Trusted Media Brands, Inc. Wordless Workshop, Workshop Tips and 泣 are trademarks of Trusted Media Brands, Inc. SUBSCRIBERS: If the U.S. Postal Service alerts us that your magazine is undeliverable, we have no further obligation unless we receive a new address within one year. CONSUMER INFORMATION: Family Handyman may share information about you with third parties for the purpose of offering products and services that may interest you. If you would rather not receive such offers via postal mail, please write to: Family Handyman Customer Mailing List, PO Box 3122, Harlan, IA 51593-0188. You can also visit www.tmbi.com/preference-center to manage your preferences and opt out of receiving such offers via email. Please see our Privacy Policy at www.tmbi.com/privacy-policy

BUY 1, GET 1

TAKE AN ADDITIONAL

WINDOWS & DOORS¹ Minimum purchase of 4.

EACH WINDOW & DOOR¹

Minimum purchase of 4.

+ \$0 MONEY DOWN, \$0 MONTHLY PAYMENTS \$0 INTEREST FOR 12 MONTHS1

Minimum purchase of 4. Interest accrues from purchase date but is waived if paid in full within 12 months.



RENEWAL **by ANDERSEN FULL-SERVICE WINDOW & DOOR REPLACEMENT**

"The whole process was simple from start to finish. The installation process was not at all stressful, and absolutely no mess was left behind. Overall, I was extremely pleased with the whole process in its entirety. Renewal by Andersen made this a very smooth and enjoyable process. I highly recommend this company for windows and doors!"

Renewal by Andersen of Colorado.

Professional window installation that creates peace of mind

All we do is replacement windows and doors, and our installers are some of the best in the business. We do it ALL for you from design to custom manufacturing to installation by our Certified Master Installers. And we back it all with the Nation's Best Warranty!† Call today for special savings!

Call by **May 31** for your FREE in-home consultation.



865-797-2513

FINDYOURWINDOW.COM

1DETAILS OF OFFER: Offer expires 5/31/2024. Not valid with other offers or prior purchases. Buy one (1) window or entry/patio door, get one (1) window or entry/patio purchase four (4) or more windows or entry/patio doors between 3/26/2024 and 5/31/2024. 40% off windows are less than or equal to lowest cost window or entry/patio door in the order. Additional \$30 off each window or entry/patio door, minimum purchase of four (4) required, taken after initial discount(s), when you purchase by 5/31/2024. Subject to credit approval. Interest is billed during the promotional period, but all interest is waived if the purchase amount is paid before the expiration of the promotional period. Financing for GreenSky® consumer loan programs is provided by federally insured, federal and state chartered financial institutions without regard to age, race, color, religion, national origin, gender, or familial status. Savings comparison based on purchase of a single unit at list price. Available at participating locations and offer applies throughout the service area. See your local Renewal by Andersen location for details. CA License CLSB #1050316. Central CA License #1096271. Florida License # CGC1527613. License #RCE-50303. OR License #198571. WA License #RENEWAW856K6. WA License #RENE only warranty among top selling window companies that meets all of the following requirements: easy to understand terms, unrestricted transferability, installation coverage, geographically unrestricted, coverage for exterior color, insect screens and hardware, and no maintenance requirement. Visit renewalbyandersen.com/nationsbest for details. "Renewal by Andersen" and all other marks where denoted are trademarks of their respective owners. © 2024 Andersen Corporation. All rights reserved. RBA 13823

