





MARCH ISSUE









COVER IMAGE BUNNINGS

Subscribe to *Handyman* p8

This issue

HANDY STUFF

Cool off in the pool and stay safe with these must-have accessories



Renovate

16 HAMPTONS STYLE

A heritage property is given a classic American makeover

25 KITCHEN MAGIC

One room gets four different treatments to suit all lifestyles


36 SPACES FOR KIDS

Create bedrooms on a budget for toddlers, tweens and teens

42 BUNK BED REVAMP

Clad a kid's bed in plywood to give it a completely new look

page 64



Outdoor

48 INSTALL A CLASSIC DECK

How to choose and lay boards to create the ideal outdoor area

54 REFINISH A DECK

Restore an old timber decking area in three simple steps

58 POWER CLEAN PAVING

The best tools you can use to restore tired pavers

60 RED-BRICK WALKWAY

Lay a path using reclaimed bricks to revive the garden

Decorate

64 UPCYCLE AND SAVE CASH

Make over preloved homewares

70 BLINDS FOR EVERY BUDGET

Pick the right window treatment

Build

73 80s GREATS

Three retro furniture projects

86 JIGSAW TABLETOP

Get creative with floor swatches

Garden

91 COMPOST FOR FREE

Save money by making your own organic fertiliser

96 HAVE HERBS AT HAND

Grow culinary herbs and freeze or dry the excess for winter use

104 PLACEMENT PERFECTION

Give your plants the right spot in the garden for a lush landscape

108 STARTING FROM SCRATCH

A bare area in the backyard becomes a vegie patch

112 NAME THAT FLOWER

Test your plant knowledge with our fun pop quiz









Getting Started

Begin with a Trust Smart Home Plug-in Starter Pack then gradually expand your system.



Trust Smart Home Alert System

Protect your home from unwanted intruders with the wireless Trust Smart Home Alert system. Easy to install and can be fully integrated into your Trust home automation system.



Trust Smart Home offers a wide range of wireless home automation products to enhance your lifestyle. Set any mood you desire at the click of a button, and you don't need to make expensive modifications to your home. See our range online at **www.trustsmarthome.com**

Trust, turning a house into a smart home.







FREE

Handyman newsletter

Get the latest DIY and garden tips in your inbox every week

> Videos Recipes Articles Projects Prizes Ideas



Sign up at handymanmagazine.co.nz

SPRINT

Stylish matte black finish



Sink Mixer SPN01 All Pressures Min. Pressure 35kpa RRP\$349



Basin Mixer SPN02 All Pressures Min. Pressure 35kpa RRP\$289



Shower Mixer SPN03 All Pressures Min. Pressure 35kpa RRP\$289



foreno.co.nz info@foreno.co.nz



WE SHOW YOU HOW! and Juna new Searan

EDITORIAL

EDITORAL DIRECTOR LYNN LEWIS MANAGING EDITOR LEE DASHIELL DEPUTY EDITOR ARTEMIS GOUROS ART DIRECTOR KATE TIMMS CHIEF SUBEDITOR AMANDA SHAW PROJECT EDITORS STUART SCOTT, ADAM WOODHAMS SENIOR EDITOR DANIEL BUTKOVICH SENIOR SUBEDITOR NICK BANKS GRAPHIC DESIGNER CONNIELEUNG FEATURES WRITER ASHLEIGH PERRIOTT WEB PRODUCER TALISA CLAVIJO DIAGRAMS STEPHEN POLLITT NEW ZEALAND EDITOR BRUCE SCOTT

ADVERTISING

GROUP ADVERTISING DIRECTOR (ANZSA) SHERON WHITE T: 61 2 9018 6280 ADVERTISING SALES MANAGER KRISTINA FROHLICH T: 61 3 8844 5542 ADVERTISING MANAGER NEW ZEALAND KERRY MCKENZIE T: 64 9 589 1054 E: kerry@hawkhurst.co.nz

MARKETING

MAGAZINE MARKETING MANAGER GALA MECHKAUSKAYTE WEBSITE MANAGER BRONWYN POVOLNY

PRODUCTION

PRODUCTION MANAGER BALAJI PARTHSARATHY T: 61 2 9018 6115

PUBLISHING

DIRECTORS WALTER BEYLEVELDT, LANCE CHRISTIE PUBLISHER, MANAGING DIRECTOR WALTER BEYLEVELDT OPERATIONS DIRECTOR ASIA PACIFIC ADINA GHERMAN

READER'S DIGEST ASSOC. INC.

T: 64 9 488 0862 E: bruce@regatta.co.nz

PRESIDENT & CEO BONNIE KINTZER VICE PRESIDENT & COO INTERNATIONAL BRIAN KENNEDY EDITOR-IN-CHIEF INTERNATIONAL MAGAZINES RAIMO MOYSA EDITOR-IN-CHIEF THE FAMILY HANDYMAN KEN COLLIER

NEW ZEALAND OFFICE

HANDYMAN MAGAZINE PO BOX 25679, ST HELIERS, AUCKLAND 1740

SUBSCRIPTION ENQUIRIES

T: 0800 400 060 E: customerservice@readersdigest.co.nz www.handymanmagazine.co.nz



PUBLISHED BY READER'S DIGEST (AUSTRALIA) PTY LTD (ABN 81000565471) 80 BAY ST, ULTIMO, NSW 2007 © 2016 READER'S DIGEST (AUSTRALIA) PTY LTD PREPRESS BY SINNOTT BROS UNIT 7, 108-120 SILVERWATER ROAD, SILVERWATER NSW 2128 PRINTED BY TIMES PRINTERS PTE LTD, 16 TUAS AVE 5, SINGAPORE 639340 DISTRIBUTED BY GORDON & GOTCH



Handyman magazine is printed on PEFC-certified paper, providing an assurance that the paper is produced from sustainably managed forest, recycled and controlled source.

All content ©2016 Reader's Digest (Australia) Pty Ltd, all rights reserved. Reproduction without permission is prohibited. All prices and information are correct at the time of printing. Prices quoted are recommended retail prices and may vary. All material sent to Handyman (whether solicited or not) will not be returned.

All do-it-yourself activities involve a degree of risk. Skills, materials, tools and site conditions vary widely. The editors have made every effort to ensure accuracy but the reader remains responsible for the selection and use of tools, materials and methods. Always obey local codes and laws, follow manufacturers' operating instructions and observe safety precautions.

Reader's Digest (Australia) Pty Limited collects your information to provide our products and services and may also use your information for the marketing purposes of RD and/or selected corporate partners. If the information is not provided you will be unable to access our products or services. Our Privacy Policy at www.readersdigest.com.au/privacy-policy contains full details on how your information is used (including how we may share your information with our affiliate companies in the US or other overseas entities), how you may access or correct information held and our privacy complaints process.

UNLEASH YOUR

CREATIVE SPIRIT









This Summer, Make It Your Own

Breathe life into everyday objects with Rust-Oleum 2X Ultra Cover. With 28 gorgeous colours to choose from, now is the time to unleash your creative spirit. Delivering twice the coverage as other competitive brands, apply it to wood, wicker, metal and plastic. The fast-dry formula resists chipping and fading, for a beautiful, long-lasting finish.



Rust-Oleum. It Simply Changes Everything







SUBSCRIBE TODAY TO



New Zearup DIV made easy

VISIT HANDYMANMAGAZINE.CO.NZ/SUBSCRIBE OR CALL 0800 400 060* MON-FRI 8.30AM TO 5.30PM AND QUOTE 'WIN A SAW-MAX'

Competition commences 25/02/16 and ends 23/03/16. Open to New Zealand residents aged 18 years or over. Drawn at the Promoter's office at 10am on 24/03/16. Winner's name published on the Promoter's website. Prizes: 3 x Dremel Saw-Max, valued at \$199 each. Promoter: Reader's Digest (Australia) Pty Ltd (ABN 81 000 565 471), 80 Bay St, Ultimo NSW 2007 Australia. Please visit www.readersdigest.co.nz/terms-and-conditions/#blanketpermits2016 for full Terms and Conditions.



*local call costs from landlines only



POOL & BEACH

ESSENTIALS

Beat the heat and cool off in the water with these must-have accessories

WORDS ASHLEIGH PERRIOTT





Splash sport

Challenge your kids to a rowdy game of Wahu Backyard Jumbo Basketball, \$77. Ideal for the pool, the kit floats on water and is easy to inflate and deflate. Suitable for kids over five, it measures 1000 x 1000 x 1800mm.

toyplanet.co.nz



Embrace a summer theme with the fresh and fruity look of the Sunnylife Inflatable Watermelon Ball, \$25. It measures 350mm in diameter and is perfect for tossing around at a pool party with the kids on a hot day.

funkygifts.co.nz



Slide time

Kids will enjoy launching into the pool or sandpit down the Swing Slide Climb Snail Slide, \$39. Measuring 1120 x 650 x 670mm, it is very portable. Made of sturdy plastic, it will stand the test of time in a Kiwi backyard.

bunnings.co.nz



Drifting donut

Let the kids cool off by floating around in their favourite tasty treat, a Junior Donut, \$19. Covered in frosting and sprinkles, this 800mm inflatable ring comes in chocolate or strawberry. It's also available in a 1200mm size, \$26.

theoriginaldonut.biz



Beat the burn

Get effective protection against the sun when picnicking with the Sommersault Pop Up Beach Shelter, \$49. Pull-cord assembly is simple and the polyester canopy is rated UPF 50+. bunnings.co.nz



DECO-DENCE



Create stunning backdrops at an affordable price, high quality deco screening now available off the shelf at Bunnings Warehouse. Use outdoors or in, easy to install, choose from a range of profiles. Visit our website for details.





Little lifesaver

Keep toddlers afloat in the swimming pool or at the beach with a Salus Bijoux Baby Life Vest, \$140. Available in four colours with an easy-to-reach lifting strap, it's designed specifically for infants and will ensure that the baby will turn face up in the water.

frogsandtoadstools.co.nz



Clear the way

Keep the pool water clear with Hy-Clor Pods, about \$14 for a two-pack. Place a pod in the pool skimmer box and the clarifier solution will treat and help clear cloudy water in 24 hours. The wrapper simply dissolves away.

hyclor.com.au

Speed shutter


Make sure the pool gate snaps shut swiftly with the G8 Safe Adjustable Pool Gate Spring Hinges, \$47 for a two-pack. Made of super-strong polymer, they won't rust, and the hinge tension is very easy to adjust.

protectoraluminium.com.au

Classy glass

Get good visibility plus a chic look poolside with an Everton 1200 x 900 x 10mm Semi Frameless Glass Gate Panel, \$175. Add the gate panel to a full glass fence for an unobstructed view of the pool.

evertonglass.co.nz



Gate guardian

The G8 Safe Lockable Pool Gate Tri Latch, \$95, has a dual-action safety button that keeps children from using implements to open it, plus mechanisms to ensure the latch is secure each time it is shut.

protectoraluminium.com.au

Salute a legendary icon of the skies...

LANCASTER BOMBER

Exclusive Masterpiece Clock

Hand-crafted **Avro Lancaster** Bomber sculpture with bronze-tone finish



Expertly hand-painted for precision detail

> **MEASURES** 25cm WIDE 16cm HIGH 15cm DEEP




70th ANNIVERSARY AVRO LANCASTER Active Service 1942

Showcasing the 617 Squadron motto 'Après Moi, Le Déluge'

Clock and thermometer inspired by the Lancaster's authentic cockpit instruments

Includes a fascinating FREE FACT CARD!



For quickest delivery, order online: www.bradford.net.nz/aircraft Quoting promotion code: 26070

In 1942, the ground-breaking Lancaster Bomber entered into RAF service, making military Ahistory as it confirmed its battle-ready status. Symbolising the combined hopes of the Allied nations, this spectacular aircraft delivered a record 608,612 tons of bombs during its remarkable 156,000 sorties, proving itself to be one of the most successful night bombers of WWII! Now you can celebrate the landmark 70th anniversary of a true icon of the skies with the perfect tribute - the Lancaster Bomber Masterpiece Clock is a collectable unique to The Bradford Exchange.

Mastercrafted by hand for authentic detail...

- · Market-first sculpture honouring the fearless Lancaster pilot Guy Gibson's iconic aircraft, flown during his command of the famed 617 Squadron.
- Authentically mastercrafted with a gleaming bronze-tone finish reminiscent of stunning museum-quality treasures.
- · Mounted on a richly grained and polished wooden base with a precision Quartz movement clock and indoor thermometer - both inspired by authentic instruments from the Lancaster's cockpit!
- Clock face inscribed with the stirring 617 Squadron motto of 'Après Moi, Le Déluge' (After Me, The Flood) - a striking reminder of the bomber's contribution to the acclaimed 'Dam Busters' raids.
- Featuring the symbolic laurel wreath of victory, in addition to a brilliant brass-like plaque proudly commemorating the Lancaster's service with the RAF!

Astounding quality and unique design - order yours today!

This anniversary edition is a one-of-a-kind celebration of an iconic aircraft and a legendary pilot. Arriving with a Certificate of Authenticity, this fine masterpiece is yours for just three interest-free instalments of only \$49.99 - that's \$149.97, plus \$14.99 postage and handling, backed by our famous 365-day guarantee. You need pay nothing now. To reserve your edition, simply complete and return the coupon or go online today at www.bradford.net.nz/aircraft

PAY NOTHING NOW

THE BRADFORD EXCHANGE

Please Respond Promptly

YES! Please reserve the "70th Anniversary Lancaster Bomber" Clock for me as described in this advertisement.

Mr/Mrs/Miss/Ms Fi	rst Name:
Surname:	
Address:	
-	Postcode:
Phone: (optional)	
Email: (optional)	

Please select your preferred reservation option:

1. MAIL no stamp required, to:	*
The Bradford Exchange, Freepost No.98331,	
PO Box 91901, Victoria Street West, Auckland	11142

2. PHONE: 09 829 0475

10am-7pm Mon - Fri

3. ONLINE at www.bradford.net.nz/aircraft

quoting promotion code: 26070

Please allow up to 10 business days for delivery. All sales subject to product availability and reservation acceptance. Credit criteria may apply. Our privacy policy is available online at www.bradford.com.au. From time to time, we may allow carefully screened companies to contact you. If you would prefer not to receive such offers, please tick this box.

What's new

Summer's winding up and March is a great time to attack the D.I.Y. projects still on your to do list. Daylight savings has not yet turned so there's still plenty of time to crack into it especially with these awesome new products.



SELF-CLEANING SHOWER Cut your bathroom cleaning time in half with the Stein Georgia Curved Shower Unit. It features Enduroshield technology which makes glass resistant to water and oil, and repels soap scum. Stein showers are made with toughened safety glass and beautifully finished with chrome plated fittings and hardware. \$899



THE PERFECT WINTER WARMER The CLICK 5000W ceramic retro mini fan heater is a stylish unit, perfect for the any room up to 10m². This tidy little number features a PTC heating element, a safety tip-over switch and overheating protection. **\$19.98**





QUALITY COOKING Create inspirational dishes with this up-to-the-minute stylish black glass gas hob and oven combo. The easy-clean black glass hob has quality cast iron trivets and a flame failure safety device on each burner. The 9 function, 65L oven has a triple-glazed door and electronic touch control. **\$1195**



controlled Heating From temperature to angle, through to timing, the AKAI 2000W Fan Heater is loaded with features that makes heating easier. It has an adjustable temperature control, overheating protection and a tip over switch. It also displays the room temperature on an easy to read blue backlit LCD display and comes with a remote for easy use. \$49.98



MOULD FREE ZONE Eliminate condensation, mould and mildew from your bathroom with the Square Stein Showerdome. It encloses the shower unit, leaving you with a healthier environment for your family. \$220



SLEEK AND EFFICIENT With a modern white gloss finish, the Sylvia White LED Spotlights are the perfect addition to any interior. With 450 lumens per head, you can adjust the spotlights to suit specific areas of your room. Available in single, double, triple or quad. Plus, see in store for a new range of spotlights to suit your design needs. From just \$49

THE ULTI-MATE STORAGE AREA





CREATE THE ULTIMATE GARAGE Make your dream garage a reality with this Ultimate setting. The cabinet doors are built from strong industrial finished Silver Checker Plate. They're also key lockable which keeps dangerous and expensive tools out of curious hands. Under bench tool chests have locking castor wheels which allows you to move heavy tools around the garage with ease. From just \$69



LESS DUST FASTER FINISH The Ryobi ONE+ 18V Random Orbital Sander Skin is cleaner than most with up to 80% dust pick-up efficiency - a quick clean up means a faster finish. It also features the Quick-Fix Hook & Loop sanding pad attachment which means you can change sand paper at speed with little effort. \$119



QUICK SAND The Ryobi ONE+ 18V Corner Sander console will get you in and out of tight spots with ease. Don't lose momentum with the Quick-Fix Hook & Loop sanding pad attachment which makes for a speedy change of sand paper. Plus, clean up is a breeze with the dust port for dust extraction. \$99



WORK BEATS Stay in tune with the Ryobi ONE+ 18V AM/FM Radio with Bluetooth Skin. Fire your playlist to the radio via Bluetooth. With a range of up to 30m, you can control your music from anywhere in your backyard. It also has an auxiliary function for MP3 use. \$109



LESS MAINTENANCE. MORE TORQUE

The Ryobi ONE+ 18V Brushless drill driver kit gives you 60Nm of torque power, which means that it can drill up to 50mm in timber. Its new brushless motor requires less maintenance but offers more run time — perfect for on the go performance. It's also compatible with all 18V ONE+ consoles, with over 40 tools in the range. \$349



BALANCED FOR COMFORT The Hart 20oz Claw
Hammer is what you need for all your projects. It's
true balanced for comfort, which means a reduction
in fatigue - this will help you power through the job
at hand. Plus, you're guaranteed with a limited lifetime
warranty. \$49.98
























rather than it being just a dead space.

backyards in doing this. A usable area

for the kids and their friends, with the

deck above where the adults can relax

Tall louvres, crisp white paint

and pendant lighting make the high

vaulted void joining the two levels

a pleasant and functional addition,

and watch over them,' says Claus.

The footprint of the house remains the same, but the new design maximises space and light

1- Garage

2- Bed

3- Office

4- Library

5- Ensuite

12- Laundry

15-Pool

16- Deck

13- Mudroom

6- Butiers Pantry

7- Kitchen

8- Lounge



Garage revamp

A common feature of a Queenslander is the carport located at the front of the property, with its purpose purely practical rather than aesthetic.

'The problem with a carport at the front is that it tends to take over, or dictate the property style,' says Claus.


'The only way to enhance and integrate what was essentially an ugly addition was to turn it into a cottage. And while used for parking, it can be easily converted into a workshop, studio or extra accommodation.

'Whatever we did with the house, we replicated on the carport. This actually makes it disappear and the house remains the standout feature.

'When you walk round this house, you don't feel like there's been a huge renovation. It looks complementary and natural, and that is I think a great indication of success,' says Claus.

'It's a true enhancement of what was already built, which is about configuring the rooms in the right positions, creating comfortable spaces to live in and maximising views.'

ABOVE Two formal stone planters form striking features in the levelled front yard. BELOW The cleverly renovated carport at the front reflects the design of the house so it blends in rather than stands out.














KIAGEN MAGGEN

Transform a dated space into a modern haven for cooking, eating and socialising

WORDS ASHLEIGH PERRIOTT AND ARTEMIS GOUROS

a family home, an outdated kitchen not only makes preparing meals more of a chore than a pleasure but also presents storage issues.

The two main elements to consider as you plan a renovation to the hub of the home are layout and lifestyle.

Your kitchen needs to be designed for maximum functionality and to suit your day-to-day life.

Budget is a key factor, so plan ahead to get the biggest bang for your buck when renovating the kitchen.

ONE KITCHEN, FOUR WAYS Before Kitchen upgrade If you have an original or even just an old kitchen, replacing it is probably The kitchen sees at the top of your renovation to-do a lot of action list, but lack of funds or motivation may be what's holding you back. every day, ageing This 70s kitchen was given four

different treatments to show just what can be done to one space, depending

Whether you want to do a DIY makeover or rip out the kitchen and start from scratch, you'll find inspiration in these designs. >

on budget and lifestyle needs.

faster with wear and tear than other areas of your home









THE START



CHOOSE THE RIGHT FILLER FOR THE RIGHT TASK WITH POLYFILLA®







Industrial design

Creating a functional space with a bit of wow factor is easy if you have

a reasonable budget to play with.

This kitchen has wide benchtops for meal preparation and an island for dining, while subway tiles paired with dark grout for the splashback make clean-up quick and easy.

New laminate benchtops have a dramatic impact but are inexpensive and easy to maintain. Stainless steel appliances and white metal pendant lights add an industrial feel.



Install task lighting for benchtops under wall cabinets







WRECKING KNIFE



Where chisel and knife combine to form the ultimate multi-purpose tool



Country escape

To set up an open-plan area that can be used for both weekday meals or casual dinner parties, a freestanding island with stools and feature lighting is key.

Guests can chat to the cook as they move effortlessly around the working triangle of sink, stove and fridge.

A double-doored pantry and under-bench cabinets and drawers help keep workstations clear, while glass-doored wall cabinets double as storage and display.



Pair neutral tones and modern appliances for a timeless look







Specialty Cleaning & Protection Solutions



Market-leading cleaning solutions specifically designed to clean, care, protect and maintain appliances and surfaces in the home.

Ideal for stainless steel, ceramic glass and solid element cook tops, stone surfaces, washing machines, dishwashers, rangehood filters and more.

The range has been tried, tested and recommended for all of the big names in the appliance business.

For more information visit www.hillmark.com.au



Contemporary classic For a luxurious, modern renovation, team stone

benchtops with timber cabinetry. Stone is not only durable, but also scratch and heat resistant.


An earthy colour palette completes the high-end simplicity of this design and complements the minimalist look. The effect is enhanced by the mirrored splashback and glass pendant lights.

For a true entertainer's delight, a butler's pantry provides essential extra storage, plus a place to wash up and prep out of sight of guests.



Set the mood with a mix of inbuilt ceiling and pendant lights







NOIR SIMPLE ELEGANCE

77% QUARTZ and 23% acrylic.

Heat proof up to 300°C. Impact resistant.

Antibacterial and extremely hygienic. 10 year warranty



NOIR 570 570 x 500 x 200 Bowl: 500 x 435 x 200 Colour: Black



NOIR 860 860 x 500 x 185 Bowl: 425 x 425 x 185 Colour: Black



NOIR 1000 1000 x 500 x 140/185 Large Bowl: 360 x 430 x 185 Small Bowl: 170 x 285 x 140 Colour: Black

For full information:

P 09 274 4393

www.totaramarketing.co.nz

sales@totaramarketing.co.nz

Spaces for kids Spaces

eeping up with your children's changing tastes can be a costly exercise if you don't select carefully when decorating their bedrooms from the start. But it's not impossible with a few tricks.

We show you how to strike the delicate balance of designing a solo space for any age that is easy to update while still ensuring a mix of essential items such as storage, your child's favourite colours and their toys.

Find furniture ideas for kids' rooms
Head to handymanmagazine.co.nz/kids-projects



brain with a creative collection of toys and accessories that will encourage them to explore their space and learn. Go for vivid colours, a range of textures and low furniture to

spark motor skills as they go from crawling to walking. >

PICTURES ITOP] ALAMY (BOTTOM) ISTOCK

magazinesdownload.com

Find more issues

37

Moulding 60 x 18mm, about

\$26 for 3m. humepine.co.nz

from Bunnings.

Make room for a desk to use as a creative space and for studying.

British Paints® Paint& Prime

Exterior

GUARANTEE against peeling, blistering & flaking



Achieve a beautiful, durable exterior finish fast.

British Paints

www.britishpaints.co.nz









bunnings.co.nz



25 YEAR GUARANTEE against peeling, blistering and flaking. See back of can for warranty conditions. This guarantee does not limit and may not necessarily exceed your rights under the Competition and Consumer Act 2010.







BUNK BED REP

Add plywood panels and repaint dated furniture for a bright new sleep palace

bunk bed has a special place in the hearts of children everywhere, and is a status symbol that represents so much more than just a place to sleep.

This simple, slatted timber bunk bed was about to be taken to the tip, when a handy friend convinced the family to give it a makeover instead.

To strengthen the structure it was clad in plywood, with window frames cut into the side panels and painted red for a fun touch.

A shelving unit was added to the base to provide storage for books.



Despite strict regulations about construction and features, on average more than 100 New Zealand children each year are injured in accidents related to bunk beds.

Before modifying a bunk bed yourself, check all the tips for safe use on the Department of Consumer Affairs website (consumeraffairs.govt.nz).

Position the bunk bed well away from any light fittings, ceiling fans, curtains, windows and other potential hazards. Always supply a ladder that meets safety standards.

DIY TIP When going over a black finish with white paint,

finish with white paint, apply a high-opacity white undercoat before adding the top coat.

nd more issues



Before

Since the original bed had become slightly rickety with time and use, the highest priority was to reinforce the structure before improving its looks.

The original 300 x 90 x 19mm braces around the lower bunk and the head and foot slats were removed, and replaced with solid 17mm thick plywood panels secured to the end of the bed using adhesive and screws.



For extra
reinforcement,
secure heavy-duty
angle brackets to
the joints between
the headboard
and bed rails


Fasteners

Secure the sides to the guard rails and the window frames with adhesive and 30mm x 8g countersunk screws. Add the shelves, backing and headboard pieces with 50mm x 8g screws.

Use 40mm x 8g screws to attach the side panels to the edges of the shelf backing.


TIP For maximum bond, sand the parts of the bed where adhesive is to be applied right back to the bare timber.

REVAMP A BUNK BED




Make the side panels

Measure and mark the window openings centred 100mm from the top and 600mm from the base of the side panels and cut out with a jigsaw. Cut frame pieces with mitred ends and secure inside the window openings using PVA adhesive and screws.



Secure the headboard

Mark the cutout positions for the existing bed rails on the headboard. Unscrew the uprights from the rails, remove the headboards and secure the uprights to the back of the new one. Reattach the rails to the uprights then secure the headboard sides and top.




Build the shelving

On the shelf sides, mark the shelf base positions 434mm from the base then every 349mm. Position and clamp the shelves, top and base between the shelf sides then drill and countersink pilot holes, securing with adhesive and screws.



6 Add the shelves and sides

Attach the backing panel to shelves with screws. Position the side panels to overhang the foot of the bed by 20mm. Cut the guard rails flush with the top window opening. Position the shelves, securing the side panels to the backing with adhesive and screws.



Attach the tubes


Mark the tube positions centred 50mm above each shelf and 30mm from the front edge of the sides. Using a 10mm brad point bit, drill holes for the tubes, securing with super glue gel. TIP Hacksaw the tubes 1-2mm short at each end so they're easier to fill over.



6 Finish the bunk beds

Scrape or sand off loose or flaking paint and sand all over with 120 grit abrasive paper. Fill all screw heads and tube holes with timber filler, then apply undercoat and two coats of semi gloss acrylic, painting the window frames in an accent colour.

BUNK BED REVAMP





BIKE RACK


Make a wall-mounted timber box to organise your bicycle and accessories

gear tidy can be a challenge, especially with more than one cyclist in the family.


This wall-mounted rack keeps your bike out of the way and also provides a home for your helmet and other gear.

The box is made from readily available 18mm laminated pine, using two 450 x 200mm side panels, two 450 x 300mm top and base panels and one 264 x 200mm back panel.

TIP Ensure there is enough clearance between the handlebars and the wall by adjusting the depth of the recess.



MARK THE RECESS Position a compass 150mm from the front edge and 120mm from the top edge of the side panels to mark a 51mm circle. Mark two lines 45mm apart, with the top line flush with the circle.



BUDGET TIP

Use inexpensive pine to

build the bike rack and


seal with marine grade

varnish if mounting to

an exterior wall.


MAKE THE HOLES Clamp the panel to a workbench and drill a 4mm pilot hole in the centre of the circle. Use a 51mm hole saw and a power drill to cut out the circle, starting slowly and increasing the speed.





© CUT THE RECESS Use a jigsaw to cut along the lines to create the recess in the side panels. Tidy up the edges using 120 grit sandpaper.

TIP Clamp an offcut to the panel to use as a guide to help cut a straight line.



ASSEMBLE THE BOX Predrill four holes along all the edges of the top and base panels, except the front. Use 10g x 30mm countersunk head timber screws to join the panels, securing one side panel after mounting.



MOUNT THE RACK Drill three holes in the back panel, then locate a wall stud using a stud finder. Attach the rack to the stud with 10g x 75mm countersunk head screws. Use masonry anchors for brick walls.

INSTALLA CLASSICEDECE Choose and lay decking boards DIY to create the ideal outdoor area for your home SAFETY TIP If you decide to lay timber boards, pick a type that is more resistant to rot and weather, like kwila or treated pine. MARCH 2016 New Zealand Handyman





Style and size

There are many different options to choose from, so consider the function of the deck when planning it, and keep it proportional to your house size.

You can attach a deck to a side of the house in the form of a balcony or a verandah, which will usually have one or more sides supported by a ledger that is secured to the house.

A wraparound deck is a type of attached deck that follows part of the perimeter of the house, while freestanding decks are self-supported on posts and bearers.

Multi-level decking can be either freestanding or attached, which is ideal for large or sloping sites.



Despite the versatility of composite boards, natural timber is still the most popular choice. The two categories are hardwood or treated pine.



Timber boards vary in density, with hardwoods often tougher to work with

HARDWOODS such as kwila, massa, jarrah, saligna, garrapa and vitex are strong, durable choices that withstand the extremes of the New Zealand climate well.


A well-designed deck can be used for dining and lounging.

Prices start at about \$7 per linear metre for 90 x 19mm kwila boards.



ACQ TREATED PINE features a greenish tinge that weathers to a light grey-brown, and is very cost effective, starting from about \$5 per linear metre.

It is extremely lightweight, making construction and transport easier, and can be stained as desired.





'Nature locked in'

Simple, cost effective and built-strong, SmartBlock™ Gabions create landscapes with enduring style.

Cubes assemble easily with spiral joiners in minutes, making the fun part...choosing what to put inside!



When you need an innovative solution for your landscaping project, 'lock in' nature with SmartBlock™ Gabion Cubes.




Available from Bunnings Stores nationwide




www.cirtex.co.nz

LAY DECKING BOARDS




Position and cut the boards

Lay five rows at a time with 50mm overhang at each end, overlapping the joints at the nearest joist. Use a combination square to mark a line on the boards for the joist positions, then cut to length with a mitresaw.



Secure the screws

Use a drill and 2mm combination countersink bit to make pilot holes at the marks, drilling only through the board if the joists are treated pine. Use a square drive bit to secure screws, adjusting the torque clutch as needed.




Mark the joist centrelines

Check the decking board joints are square and centred over the joists, then position a straightedge or spirit level across the decking boards at the centre of each joist to mark the centrelines.



6 Check the alignment

Position a stringline along the complete length of a row, every five rows, to check the boards are straight, adjusting if needed. Use a chisel to prise the gaps slightly further open or closed as required for even spacing.



3 Mark the screw positions

Use a 40mm square offcut as a spacer to mark across the lines, showing drilling points. Make narrow wedges 100mm long using a mitresaw, then tap them between the boards at every second joist to keep the gaps even.



6 Trim the board ends

Mark a cut line on the end of the boards, leaving a 20mm overhang. Cut using a circular saw and round over with 120 grit abrasive paper.

TIP Use a handsaw to cut the last board where the circular saw won't reach.



...For 75% LESS vs cost of bottled gas.

Heatstrip® by Thermofilm is the cost effective electric radiant heater that unites efficiency with style. Ideal for your alfresco and outdoor entertaining area, pergola, patio, balcony. Even your garage, shed or hard-to-heat indoor space.

Heatstrip runs at a quarter of the cost of bottled gas, is more efficient over a larger area and won't corrode. It's easy to install and operate, an optional controller adjusts the timer and warmth levels. For more information go to www.heatstrip.com.au









phone: +613 9562 3455 email: sales@heatstrip.com.au











Spray the deck

Rinse the timber boards using a water blaster to remove any surface dirt and grime. Use a fan spray to clean the deck rather than blasting it, making sure not to be too aggressive with the water blaster.



Scrub the boards

While the deck is still wet, scrub it thoroughly with a mild detergent using a long-handled scrubbing brush, cleaning the boards of any patches of mud or dirt. Rinse off the detergent, then allow the deck to dry.



3 Apply the stain

Finish the boards with two coats of timber stain, using a decking brush or roller to spread the stain evenly all over the deck. Allow at least two hours between coats. Avoid staining the boards in hot and windy conditions.



and water easily loosens and removes the dirt which saves you an enormous amount of time and effort in comparison to cleaning vehicles with a hose and sponge.



makes a difference

POWER CLEAN POWER CLEAN

Turn the tricky task of cleaning pavers into a pleasure by using a water blaster

WORDS AND PICTURES ADAM WOODHAMS

weather, pavers can start to look a little worse for wear.

But you don't have to spend hours on your hands and knees with a scrubbing brush. You can have them looking near-new in no time using a couple of power tools.

In summer, always check water restrictions in your area and connect your water blaster to a rainwater tank if you have one.

Before

CANTIEN CANTIEN

Silvan Selecta Chapin 8L Pro XP Series Hand Sprayer, \$115. silvan.com.au

SEUCTR

CHAPIN

30 Seconds Outdoor Cleaner Concentrate, \$19 for 5L. 30seconds.co.nz

Karcher K2 Plus 1600psi Water Blaster, \$199. karcher.co.nz

ADAM'S

PICKS

Victa V Force+ 40V Lithium Blower and Vacuum, \$519. victa.com/nz



CL OT


After
Cleaned and hosed with a water blaster, the pavers are restored to their original condition.



Clear the area

Remove all the furniture, pots and any other items that are standing on the paved area to be cleaned.

Thoroughly clear the space of any loose material using either a blower or a broom and a rake.





2 Prepare the cleaner

Mix an outdoor cleaner with water in a hand sprayer container, following the manufacturer's directions and safety precautions. Avoid contact with skin, clothing and fabrics, as many products have a bleaching action.



3 Apply the cleaner

Apply the prepared cleaner over the entire paved area to be cleaned, making sure all surfaces are well wetted with the solution.


TIP On hot or sunny days, or for large spaces, only treat a section at a time.



Spray the paving

Working towards the area where water will run off, commence spraying with a water blaster, using a broom to clear the area as you go if needed.

A second going-over may be required to fully remove dislodged material.



Use reclaimed bricks to create a rustic path with a circular design at the start

WORDS AND PICTURES MELISSA DARR

hen blogger Melissa Darr moved into her house, the garden at the back was scruffy and underused, and she decided that it needed a DIY upgrade to give it a charming rustic feel.

Melissa and her husband Bevan chose to clear the existing outdoor space and lay a path of reclaimed red bricks, planted on either side with beds of herbs and vegetables.

They sourced the bricks from a nearby demolition site with the permission of the site foreman.

'We also wanted to incorporate a circular brick design at the entrance of the path where we could put a small cafe-style setting,' says Melissa.

'Now it's finished, we love to sit out there once the sun has gone down and enjoy our dinner in the twilight.'

To finish off the space, a bench that was handcrafted from the trunk of an old tree was added. For a focal point, a weathered-look terracotta planter was placed at the end of the path.



EXPERT SECRETS

Plant herbs with striking blooms, such as chamomile and garlic chives, so your herb garden doubles as a flower bed.







Clear the area The garden at the back of the house had been allowed to


grow wild by the previous owner, so the first job was to clear it completely of hard roots and shrubs.

Before Melissa and Bevan could start laying the pathway, they had to manually strip the reclaimed bricks of mortar using a hammer and bolster.

'This was a bit of a painful process, as we had about 400 bricks, but it was well worth it,' says Melissa.

A bed of crusher dust was spread over the area to be paved to provide a stable foundation for the bricks.

With the circle finished, the other bricks were added.



The circular pattern was laid first on marked lines.

Lay the bricks Melissa had her sights set on creating a decorative circular pattern at the start of the new path.

To mark out the design, a stake was pegged where the centre of the circle would be, with a length of string attached. A sharp object was tied to the string and the circle was drawn by winding the string around the stake.

Bevan began by laying the inner circle of bricks on the marked lines, working outwards from the centre.

The centre of the circle was filled in with roughly cut bricks, then the remainder of the path was laid.

Get more DIY from Melissa Follow her blog thewhimsicalwife.com



PLANT IT UP

A length of flexible drainage pipe was installed around the garden beds before the bricks were laid to irrigate the plants with greywater from the washing machine.

Melissa then planted basil, mustard greens, shallots, thyme, oregano, marjoram, chamomile, garlic chives, sage, tarragon, rosemary, parsley, mint, lettuces and spring onions.

'Our herbs have really taken off now that the warmer weather has started to hit,' she says.





Will you be our Guardians?

Taking action for animals

Each year SPCA Auckland helps more than 15,000 sick, injured and abandoned animals. With no funding from the government we rely on supporters in the community to help us do our work.



SPCA Guardians are a special group of regular monthly donors who help us take action for animals in five key ways:

- Prevent cruelty
- Rescue
- Rehabilitate
- Shelter and rehome
- Seek justice

For more information about becoming an SPCA Guardian, please visit our website www.spcaauckland.org.nz email guardians@spca.org.nz or phone og 256 7307

Revive favourite old pieces of furniture or scour op-shops, garage sales and council clean-ups for bargains to do up PROJECTS AMANDA SHAW AND TRACY MARYON PICTURES SUE FERRIS STYLING GEMA BENEITEZ

re you bored with the same old bedside tables? Before getting rid of them and buying new ones, consider upcycling them for a totally new look.

Or maybe you've been hanging onto that favourite wicker table with the cracked glass top, but don't really know what to do with it now.

Here we created a unique planter out of an old metal colander, gave outdated mahogany bedside cabinets a new paint finish and turned a wicker table into an oversized ottoman.

We also transformed a plain basket into a place fit for a princess pussycat.

You can use the same techniques to make over just about anything.



SECRETS

When giving furniture a distressed paint finish, sand the edges lightly until you achieve the desired look.



Whatever you have in your home that you think is past its prime can easily be given a new lease of life





Rockdale Coconut Fibre, \$26 for 1kg, from Bunnings.



Gardman Epoxy-Coated Replacement Basket Chain, about \$6. horticom.co.nz



Flexovit 100mm x 1m Medium 120 Grit Timber Sandpaper Roll, about \$3. abrasives.net.nz



Rust-Oleum 2X Ultra Cover Paint + Primer in Satin Gloss, \$13 for 340g. haydn.co.nz ② Dulux Duramax Metallic Finish in Gold, about \$17 for 325g. dulux.co.nz 3 White Knight Super Chrome, \$19 for 300g. whiteknightpaints.co.nz

Dulux Duramax Enamel in Endless Dusk, \$14 for 340g.

You may have an old colander like this lying at the bottom of your kitchen drawers or even packed away in storage.

If not, they can often be picked up second-hand for about \$10. Or a friend or neighbour may have a free one awaiting a council collection. This chipped red one was a great find among a heap of discarded items.

We've put it to good use as a novel planter and hung it from a tree.

All you need is exterior spray paint, a chain with an S-hook, coconut fibre, potting mix and a plant.

Attach the chain by inserting the attached clips into the holes around the colander. Spray it in metallic gold paint, line the base and sides with coconut fibre, then add the potting mix and a flowering plant.



Before

PICTURES (BEFORE) TRACY MARYON (CENTRE LEFT) AMANDA SHAW

After

Painted and potted up, the shiny gold planter adds colour to a dull corner of the garden.





Discovered by the side of the road, this sorry-looking relic was missing its top. As replacing the glass could be costly, we decided to give it a new function as an ottoman.

All it needed was high-density foam, which was cut to fit by the supplier, and a length of fabric.

The wicker base was then sprayed in a gloss white to freshen it up. The fabric was cut to fit around the foam and stitched in position.

All it took was fabric and foam to transform this preloved piece into a great outdoor accessory



PUSSYCAT BASKET

SEFFERETTIE

Does your precious feline friend need a comfy place to hang out, somewhere special she can call her own? Then this posh palace could be just the thing.

And should she need to visit the vet, an incredible carriage awaits her.

Found in bad repair, this basket was lovingly renovated with paint, fabric, a cushion insert, ribbon, cat collars, particleboard letters and glitter, plus the essential mouse house guest.

Spray the basket all over in pink and paint the handle in a contrasting grey colour. To give a glittery effect, we used a specialty spray paint in silver.

Make a mattress by covering a cushion insert with fabric. We chose a sequinned material in dark pink for contrast and extra glam.

To decorate, tie two cat collars onto the door, then secure the door to the top of the basket with lengths of ribbon, tied in bows.

Stick particleboard letters, available from Spotlight, on the top of the basket to form a name plate.

For extra bling, add diamanté self-adhesive transfers to the letters and handle of the basket, available from arts and craft stores.

DIY TIP

Choose paint and fabric in colours and textures to suit the breed and temperament of your cat.



After

Decorated with paint and bright accessories, any proud cat would be happy to call this home.



Life in colour starts with ScotchBlue."

- ScotchBlue™ Painters Tape delivers super sharp paint lines, giving you the edge you deserve
- Ideal for a variety of surfaces from freshly painted*, to glass, metal, wood and vinyl wallpaper
- Choose between 14 or 60-day clean removal
- * At least 24 hours old.







Learn more at ScotchBlue.com



BLINDS FOR EVERY BUDGET

Update living spaces with a new look for windows, choosing a blind that complements your style

to heat retention and deflection, window blinds are available in styles to suit every space and budget.

Blinds should be both decorative and functional. Wider, horizontal blinds create the illusion of bigger windows and more space in a room.



Roman blinds modernise a living space and give total block-out from light.



Follow Handyman magazine

online oppo

















FACEBOOK facebook.com/HandymanMagazine

Get handy DIY

hints and clever life hacks every day





Share our tips with your friends

PINTERST

Browse our boards

for DIY inspiration




Repin your favourites to your own boards

INSTAGRAM @HandymanMagazine

Get inspired while on the go



- Follow @HandymanMagazine
- Like your favourite pics
- Tag us in your DIY shots







Long before the iPod, portable music was made possible by the Compact Cassette.

The proportions of this tribute table are almost identical to those of the original Philips cassette tape and it even has spools. It features a drawer for storage and a 6mm acrylic top.

It's built from overlapping layers of plywood that are initially secured with screws. The central layer is made from two pieces joined edge-to-edge, making it easier to drill into the spools. TIP To cut out the enclosed shapes with a jigsaw, drill a 10mm starter hole.


What you need

Structural plywood
Clear acrylic
Countersunk timber screws
Pine dowel
Drawer runners
Clear surface savers
Chrome legs
Varnish stain
Clear polyurethane


Install the drawer

The drawer runs on self-closing 300mm runners, which will extend about 50mm behind the drawer, allowing it to slide out almost fully.

Secure the runners to the drawer sides using the supplied screws, then mark the position of




MAKE THE TABLE




Assemble the pieces

Cut the pieces with a circular saw and number them, round the corners and cut the details with a jigsaw. Put the first and second layer on the base panel, checking the outer edges are flush, then secure with screws. Repeat for the third and fourth layers. Don't join areas where the back and sides overlap.




Make the drawer

Use a circular saw to cut a 3 x 3mm groove 9mm from the base of the drawer front. Secure the drawer back to the sides using adhesive and screws, then attach the base, leaving a 3mm lip at the front. Apply adhesive and slot the drawer into the groove on the back of the drawer front, adding the handles.



Sand the components

Ease the three main sections apart, then clamp each of them in turn and sand the outside smooth using a belt sander. Assemble the core stack, omitting the central spool layer, then use a rasp and 80 then 120 grit paper to shape the opening of each spool into a smooth curve.




60 Glue the layers

Separate the sides and back of the table. On a flat surface, apply PVA adhesive to the base and position the layers, securing them with screws. Secure the drawer runners and glue the core in position, then add the top. Sand the top and base flush with the openings and edges of the inner layers.



3 Complete the spools


Use a 12mm spade bit to drill 10mm deep holes for the spool teeth, then apply PVA adhesive and tap in the dowels. Apply limewash, then secure the spool layer between the other layers of the core. Glue the tape plates in position. Sand flush with the spool layer and apply varnish stain.



Made the top and legs

Use a jigsaw on low revs with the pendulum action switched off to cut the acrylic to shape. Use a coping saw to cut the openings in the interface covers, securing with adhesive. Apply two coats of clear polyurethane, then cut the legs to length. Secure them using the supplied screws.

CASSETTE TABLE measurements in mm



PART	SIZE	NO
Plywood		
Long back	1000 x 100 x 17	2
Short back	624 x 100 x 17	2
Long sides	610 x 188 x 17	2
Short sides	510 x 188 x 17	2
Long railed sides	610 x 198 x 17	2
Short railed sides	510 x 198 x 17	2
Top/base	1000 x 610 x 9	2
Outer core	570 x 180 x 9	2
Inner core	600 x 180 x 17	2
Spool front	600 x 74 x 17	1

Spool back	600 x 106 x 17	1
Drawer face	635 x 80 x 9	1
Drawer back	600 x 55 x 9	1
Drawer sides	230 x 55 x 17	2
Drawer base	600 x 242 x 3	1
Drawer handles	130 x 80 x 17	2
Tape plates	125 x 88 x 9	4
Interface covers	795 x 150 x 9	2
Dowel		
Spool teeth	20 x 12	12
Acrylic		
Clear top	1000 x 610 x 3	1

♥ FASTENERS		
TYPE	USE	
Timber screws, 30mm x 8g	Securing layers	
Timber screws, 20mm x 4g	Drawer back to sides	



GO FOR LAUNCH

Persuading kids to put away their toys can be a battle, but giving them a rocket storage cabinet makes the job a lot more fun.

We used an orbiter vehicle (OV) from a NASA space shuttle as the inspiration for this cabinet.

The shape of the aerofoils and fuselage were simplified, but the overall proportions are faithful to the original orbiter.

The cabinet was built as a carcass attached to a backing sheet cut into the silhouette of the fuselage and wing shape, called the planform. The doors and cabin are clad in Corflute, a plastic version of corrugated cardboard.



The vertical stabiliser is often referred to as a tail fin for simplicity, even by pilots

What you need

Timber
Paint, filler, marker
Screws, tacks, hinges
Self-adhesive sheet
Corflute
Copolymer sealant
Chrome cabinet pulls
Magnetic catch
Plastic tumblers
Dowel

Finishing touches

To decorate the orbiter vehicle, download the cabin markings, then print them on self-adhesive paper and apply to the cabinet.

The easiest way to mark the details on the wing trailing edges is to simply draw them on with a paint marker such as a Posca.

Plastic drink tumblers from the supermarket painted black make excellent engine nozzles.

To keep the doors shut and make them easier to open, attach a magnetic catch and a pair of brushed chrome cabinet pulls.



Zenith 8g x 30mm Zinc-plated Long Thread Timber Screws, about \$5 for 30, from Bunnings.




White Knight Splashes Water-based Enamel, \$12 for 250ml. whiteknightpaints.co.nz



Balsa 300 x 100 x 50mm Blocks, \$19 each. tasart.co.nz



BUILD THE CABINET



Cut the pieces

Make templates for the shelves, door ribs and cabin supports, marking them on plywood and cutting out with a jigsaw. Use a pull saw to tidy up the notches in the ends of the door ribs. Cut the sides using a circular saw.



Add the infill stiles

Apply adhesive to the door frames, then attach the infill stiles and base ribs, clamping in position. Use a jigsaw to cut a blank for the nose cap from an offcut of 90 x 35mm timber and shape it into a convex profile using a rasp.



Secure the planform

Mark the planform on a sheet of 12mm plywood, then cut out using a jigsaw. Apply primer and two coats of paint to the carcass, leaving the back edges, then paint the planform. Leave to dry. Secure the carcass with adhesive and screws.



Assemble the carcass

Clamp the shelves between the sides, securing with screws and PVA adhesive. Secure the divider/tail fin between the base and first shelf with adhesive and screws. Trim the base ribs to fit on each side of the tail with 2mm clearance.



Build the cabin frame

Use a sliding bevel to mark 23° angles on the sides, cutting a 17 x 15mm notch in each end. Bevel the front and back supports at 50° with a belt sander, then cut matching notches. Glue the collar to the back and supports to the sides.




Cut a groove in the nose cap edge for the barrel of a non-mortise hinge. Sand with 120 grit paper, then prime and

paint. Glue and screw to the front cabin support and hang on the planform. Hang the cargo bay doors using hinges.



Use a pull saw or dovetail saw to make relief cuts for 17 x 15mm half-lap housings in the stiles, then chisel out the waste. Position the stiles and apply adhesive, gluing all but the base pair of ribs into the housings.



Clad the doors and cabin


Prime and paint the door and cabin frames. Use a utility knife to cut the Corflute, scoring along the crease lines of the cabin. Bend the cladding to shape then use copolymer sealant and cut tacks to secure it.



Attach the engines

Cut the OMS pods and make the nozzles using a 35mm holesaw. Shape the pods and nozzles using 80 grit paper, drilling 8mm holes to secure with dowels and adhesive. Attach the pods using sealant, and the main nozzles with screws. >

ORBITER CABINET




TYPE	USE	
Countersunk timber screws, 30mm x 8g	Carcass assembly, planform attachment	
Countersunk timber screws, 18mm x 4g	Hinges	
Round head screws, 15mm x 8g	Main engine nozzles	
Cut tacks, 12 x 1.6mm	Cladding	
Non-mortise hinge, 50mm	Nose cap	
Piano hinges, 915mm	Cargo doors	

© CUTTING LIST			
PART	SIZE	NO	
Plywood			
Sides	1000 x 150 x 17	2	
Shelves and door ribs	300 x 266 x 17	5	
Divider/tail fin	450 x 370 x 17	1	
Front cabin support	100 x 80 x 17	1	
Back cabin support	300 x 300 x 17	1	
Cabin collar	300 x 300 x 17	1	
Planform	1500 x 900 x 12	1	
DAR Pine			
Stiles	1000 x 30 x 18	2	
Short stiles	745 x 30 x 18	2	
Infill stiles	235 x 30 x 18	2	
Cabin frame sides	355 x 30 x 18	2	
Nose cap	90 x 80 x 35	1	
Corflute			
Main door cladding	735 x 225 x 3	2	
Rear door cladding	265 x 215 x 3	2	
Cabin cladding	480 x 480 x 3	1	
Balsa			
OMS pods	250 x 100 x 50	2	
OMS nozzles	50 x 35 diameter	2	





BUILD THE SHELVES




Out the pieces

Use a circular saw to cut the individual pieces. Mark the interlocking notches on the ends with a combination square, cutting them with a jigsaw. Cut square 90 x 90 x 45mm blocks from 90 x 45mm timber, then cut a notch out of one corner of each block, making the blocks into L shapes.



Complete the pieces

Test-fit the pieces and check for square, then use corner clamps to hold the pieces in alignment. Use a drill with an 8mm brad point bit to bore holes 36mm deep into the joints. Loosen the clamps and apply adhesive then tap in the dowels and leave to dry.



Assemble the corners

Apply PVA adhesive to the joining pieces of the internal corners of the shelving. Align them at 90° using the L-shaped corner blocks held in position with F clamps. Use an 8mm brad point bit to bore 40mm holes in the overlapping joints. Glue in 38 x 8mm dowels, leave to dry, then fill over.



Trim and sand

Once the adhesive is dry, remove the clamps and use a pull saw or oscillating tool to cut the dowels flush with the exterior surfaces.

Apply timber filler in a suitable colour to cover any gaps and imperfections, then sand any excess filler flush with the surface using 120 grit paper.



Paint the interiors


The interiors of the shapes will be awkward to paint after assembly, so apply the finish first. Sand lightly with 120 grit paper, wipe clean, then mask off the interlocking surfaces. Use a brush or roller to apply primer, then finish with two coats of spray paint in the colours of your choice.



6 Sand and finish

Use a belt sander with an 80 grit then 120 grit belt to sand the corners smooth and even up the edges, finishing with a random orbital sander. Mask off the interiors and apply stain or clear polyurethane to the exterior surfaces of the shapes, sanding lightly between coats.

TETRIS SHELVES measurements in mm



JASSAW TABLETOP

Design a new top for an old frame using laminate floor swatches

WORDS FRANK GARDNER STYLING GEMA BENEITEZ MAIN PICTURE SUE FERRIS

table was in good condition, but the glass top had been broken and needed replacing.

Cutting a new piece of glass to size would have been expensive, so the top was replaced with a creative solution for a fraction of the cost.

Ten 355 x 195mm laminate floating floor swatches in a variety

of colours and grains were bought for \$1 each from the hardware store.

The swatches were arranged on a 9mm thick MDF backing board and attached with contact adhesive.

To cut the swatch board into pieces, a tablesaw was used to maintain 90° corners and straight edges. The pieces were then attached to a second MDF board to create the tabletop.



The new tabletop cost less than \$30 and took just three hours to make







Secure the swatches

Use the supplied notched applicator to apply contact adhesive to a 9mm MDF board and the underside of the swatches, then leave until touch dry. Position the swatches, aligning their edges carefully, then press firmly.



2 Cut the pieces

Use a tablesaw to cut the swatches into rectangles and squares of varying sizes, maintaining pressure against the fence to ensure square cuts.

TIP Use a push stick to guide the board past the blade for safety.



3 Make the top

Arrange the laminate pieces on a second piece of 9mm MDF board, securing them in position with PVA adhesive, keeping the butt joints tight. Clamp until dry, then secure the top to the table frame using screws.



Handyman

BUYER'S GUIDE

Take the DIY option for your home improvement projects by choosing the best tools and equipment from our market round-up













Handyman BUYER'S GUIDE




Heat your entertaining area for 75% less than bottled gas with 100% more style.

Heatstrip® by Thermofilm is the cost effective electric radiant heater that unites efficiency with style. Ideal for your al-fresco and outdoor entertaining area, pergola, patio, balcony. Even your garage, shed or hard-to-heat indoor space. Heatstrip runs at a quarter of the cost of bottled gas. It's easy to install, an optional controller adjusts the timer and warmth levels. For more information go to www.heatstrip.com.au



address: 27 Rosalie Street, Springvale Victoria, Australia 3171 phone: +613 9562 3455 email:sales@heatstrip.com.au











MAINTAIN THE HEAP

The traditional way to create a compost heap is to layer it.

- START with a 300mm layer of plant waste, followed by a thin layer of manure or blood and bone, then add a thin layer of topsoil.
- O INCLUDE a layer of dolomite or lime if you want an alkaline compost.
- CONTINUE adding to the compost in layers until the heap reaches a height of about 1m.
- KEEP the heap damp rather than mushy and don't mat it down, as this will impede aeration and make it smell.
- TURN the heap regularly. The more frequently you turn the heap, the quicker your compost will be ready.
- **MOVE** the outer sections into the middle where the heat is while turning, so they will decay fully.



Ready to go

When compost is a rich, dark colour, with a pleasant, earthy smell and a crumbly texture, it's ready to use.

Dig it into the soil before planting or use it as a mulch. If it's finished before you need to use it, cover it with plastic to prevent the nutrients from leaching away. >







to a lush and healthy garden



soil prep before planting

regular mulching



less watering

www.daltons.co.nz

WHAT CAN GO WRONG?

Seedlings appear

Large numbers of seedlings in your compost means the heap isn't hot enough. Cover it with punctured black plastic or old carpet to retain more of the heat.



It's too wet or too dry

When the compost is too wet, add dry shredded newspaper, leaves or straw to dry it out. If it's too dry, add manure, blood and bone, and other nitrogen-rich ingredients.

The heap won't get hot

When the heap doesn't heat up, it lacks nitrogen. Add materials like grass clippings, manure or blood and bone. Turn it regularly and use insulating material in winter.



There's a bad smell

A lack of air or carbon in the heap will cause it to smell. Add dead leaves, stems, sawdust or straw and turn the heap. Use dolomite or wood ash to reduce acidity.



Rodents move in

To prevent an infestation of rats or mice, cover the compost with underfelt, hessian or plastic. Turn it regularly and don't add seafood, dairy products or meat to the heap.



Weeds take over

Seal annual weeds that have gone to seed, and perennial and bulbous weeds, in a plastic bag with a little water. Cook in the sun for a month before adding to the heap.





Create lawn envy in your neighbourhood with Burnet's premium range of lawn seed and care products. New look pack, same excellent quality seed.





You don't need green thumbs to grow most herbs and you don't even need a garden, as they grow well in pots when given adequate space.

Dedicating an area to herbs close by the kitchen door is an ideal way to make night harvesting easy. But if you don't have room for this, you can just plant them in the vegetable patch and flowerbeds.

Coriander, rocket, parsley and mint will tolerate a little shade, but give other herbs the sunniest position available, with well-drained soil or a good-quality potting mix. >

Summer cuts

Pick herbs regularly during

branching and autumn growth,

and remove the flowers when

they appear to encourage new

usable leaves for the kitchen.



WHAT TO PLANT

PERENNIALS

While most perennial herbs are evergreen, providing leaves all year, it's a good idea to preserve a quantity for winter when growth is slow.

They like well-drained soil and need less water than annuals. Feed them in spring and summer with a three-month controlled-release fertiliser.

Chives

Chives are easy to grow in beds and containers. Garlic chives have flat containers and don't die down in winter. leaves and don't die down in winter. The flowers make a great garnish.

- o GROW Sow the seeds in summer and early autumn. Divide clumps every second year in early spring.
- O HARVEST Use the leaves fresh, or chop and freeze in ice cube trays.

Bay leaf

Fresh or dried bay leaves are essential to add flavour to soups, casseroles and stews.

- GROW In a garden bed, this small evergreen tree can reach a height of 11m, but it can be pruned lower or shaped for container cultivation.
- HARVEST Use fresh, or freeze or dry whole leaves.

Lemongrass

The white base of the leaf is widely used in Asian cuisine and the leaves make a refreshing tea.

- GROW The 1.5m long leaves of this easy-to-grow clumping grass make a statement planted in garden beds or large pots.
- HARVEST Pick the stalks as needed, either cutting or snapping them off at ground level.

Marjoram

The oval-shaped leaves of this herb are used for flavouring meat and pasta dishes, and the small white flowers make a great garnish.

• GROW Prune off flowerheads

- when they appear for a good supply of leaves. Keep the soil moist.

 HARVEST Use the leaves for
- HARVEST Use the leaves fresh, freeze in oil, or dry them.

- GROW Plant in a damp spot or in a pot and stand in a saucer of water. Mint can be grown in semi-shade.
- O HARVEST Use the leaves fresh, or freeze or dry them.

Oregano

The leaves of this spreading herb work well in Italian dishes and soups and stews. The small purple flowers make a pretty garnish.

- GROW Cut off spent flowerheads to encourage more leaves. Harvest the leaves now for drying to promote more growth throughout autumn.
- HARVEST Use the leaves fresh, freeze in oil, or dry them.

Sage

The grey-green leaves of sage team well with duck, poultry, casseroles and soups.

- GROW It needs well-drained soil and good air movement around it to perform well. Prune back the stems when the flowers have finished.
- HARVEST Use the leaves fresh, freeze in oil, or dry them.

Rosemary

Used with lamb and other meats, the leaves are also great sprinkled on roast vegies or added to tomato soup. GROW It reaches about 1.5m high but can be pruned back. There are groundcover types that can be grown in pots. It likes a slightly alkaline soil and is very drought-tolerant. O HARVEST Use the leaves fresh, freeze, or dry them.

Thyme

This herb teams well with Italian dishes, soups and stews. Lemon thyme goes well with fish and you can also grow 'Pizza' thyme.

- GROW After flowering, lightly trim to encourage more leaves and extend its life span. The flowers can be eaten and used as a garnish.
- HARVEST Use the leaves fresh, freeze in oil, or dry them. >

ANNUALS Treat annual herbs as you would

salad vegetables and give them plenty of food and water.

Before planting, enrich the soil with compost or cow manure, then water regularly and feed fortnightly with a soluble complete plant food to encourage new leaves.

Chervil

The parsley-like leaves of this herb have a mild aniseed flavour. Chop and add to dishes just before serving, as heat diminishes the flavour.

- GROW It likes a semi-shaded spot in moist soil and, if you let one plant go to seed, it will reappear annually. Sow the seeds until early autumn.
- O HARVEST Use the leaves fresh.

Basil

There are many different types of basil suited to a variety of cooking styles. Plant 'Lemon' or 'Thai' basil if you like Asian cuisine.

- GROW Get seedlings in the ground now to enjoy the leaves until the cool weather arrives.
- HARVEST Use fresh or chop and freeze in ice cube trays.

Parsley

Grow biennial curly or flat-leafed parsley for use in summer salads, soups and casseroles.

- GROW Plant seedlings or grow from seed. Parsley is a very greedy herb, so regular feeding is essential to keep it producing leaves.
- O HARVEST Use fresh or chop and freeze in ice cube trays.

Widest range of seed varieties

- Packed in **New Zealand**
- Growing guarantee
- **GMO Free**





Available at
Bunnings
and independent
garden centres
nationwide



bunnings.co.nz





DRYING

Herbs can be dried in dehydrators or air-dried in bunches. They can also be dried in the oven.

• AIR-DRY Strip the lower leaves from the stems and tie 6-8 stems together with a rubber band or twist ties.

Hang in a dry, well-ventilated spot until the leaves are dry and crumbly. Remove and store in an airtight tin or bottle away from bright light.

Air-drying ensures that the herbs maintain their essential oils.

OVEN-DRY Strip the leaves from the stems and spread on an oven tray. Put in the oven at its lowest setting, leaving the door ajar to let moisture escape.

After 30 minutes, turn over and leave for a further 30 minutes or until dry. Remove from the oven and allow to cool. Store in an airtight container.




Dried herbs keep their taste for about a year

Drying seeds Caraway, fennel, coriander and dill seeds can be added to many dishes. To dry, cut the stem when the seed heads turn brown. Tie 3-4 stems together and hang upside down in

together and hang upside down to together and hang upside down to the a paper bag. When dry, separate the seeds and store in airtight containers.













A green hedge is ideal for hiding ugly views and providing privacy. But pick carefully or you could end up in an unending battle to control its growth.

One of the worst is the Leyland cypress (X *Cupressocyparis leylandii*), which has been the cause of many neighbourhood disputes.

But aside from upsetting neighbours by blocking light and views, it is fast growing and needs constant pruning. If left unpruned, it can grow to 20m.

There are lots of well-behaved options, including eugenia, camellia, box-leaved honeysuckle, pittosporum, oleander, silver-leaved *Teucrium* fruticans, photinia, *Viburnum tinus* or blue-flowering plumbago.

Scented choices such as murraya, osmanthus and port wine magnolia (*Michelia figo*) will make both you and your neighbours feel good.



Not only do they provide shade, wind protection, clean air and a habitat for wildlife, trees beautify the landscape.

As with plants, they need to be planted in a spot and climate that suits them or they may not cope with the extremes of moisture or temperature and will never look healthy.

Before buying, research the height, width and growth habits of a tree at maturity, as that small stick-like plant you took home from the nursery could reach an enormous height.

Trees, such as jacaranda, casuarina poplar, liquid amber and fig, can also create problems if planted too close to foundations or over sewerage pipes.

Varieties such as citrus, frangipani, flowering plum, crepe myrtle and olive are ideal for a small yard.

STARTING FROM SCRATCH

After lots of trial and error, a lush vegie and herb garden emerged from a patch of scrubby lawn

WORDS SITA SIMONS

aced with a bare patch of land, it was determination and a can-do attitude that saw Amelia van Zyl create an abundant vegetable garden, one that feeds her family of four and provides extra for her neighbours.

With no real gardening experience, Amelia read countless books and talked to friends and professionals.

'It was so awful to look at, it really motivated me to do something with it, and quickly,' says Amelia.

'I look back now and see my lack of experience as a blessing, as I wasn't fearful of messing anything up. This is the garden that trial, error and a big dose of good luck built.'

LEFT Raised levels and beds provide a vegie garden with structure.
RIGHT Team tomatoes and basil for a classic culinary combination.





magazinesdownload.com

Sow it and see

The best vegetable gardens are busy and productive, and this doesn't require precision planning.

Landscape gardener Jarret Clynick advises a sow-it-and-see approach for the best long-term results.

'If you're starting from scratch, as Amelia was, first get your expectations in check. Don't imagine you will have a bountiful vegetable garden within the first few seasons,' says Jarret.

'Choose three or four things you really want and plant multiple packs of seeds. This allows you to see what will thrive and what won't.

'Build on your food garden layer by layer. If you stick with it, you will be rewarded with abundance,' he says.



Maximise your yields and variety of plants by building up with simple trellis structures





D.I.Y. Workshops

Brush up your knowledge and gain new D.I.Y. skills with workshops in-store and online.

Our workshops are held every weekend on Saturday and Sunday from 11am - 1pm for Adults and Kid's sessions from 10am-2pm. Covering a wide range of topics, these workshops are heaps of fun, suitable for all levels of experience and a great way to learn new tips and tricks.

If you can't make a session, don't worry – we have heaps of step-by-step guides and expert help in-store, plus handy on-line videos 24/7.



Here are just some of the handy on-line videos available at bunnings.co.nz

HOW TO BUILD A RAISED GARDEN BED A step by step guide to enhance your garden.	REPAIR HOLES IN PLASTER A simple project with the right tools and instructions.
HOW TO LAY PAVING Create an ideal environment for your home and garden.	GET CREATIVE IN THE KITCHEN When it comes to designing your dream kitchen, we can help you every step of the way.
BUILD A GARDEN TRELLIS Perfect for displaying a great variety of creepers.	HOW TO BUILD SHELVING Check out this simple shelving project for the home office.
USE A ROUTER Using a router for the first time can be a difficult task, but we'll make it easy.	HOW TO CHILD PROOF A HOME Protect your child from hazards at home.
MAKE THE MOST OF YOUR PANTRY Make it easier to find what you need in your kitchen.	WHEN TO PLANT IN NEW ZEALAND Gardening advice designed to help you save time, effort and money.





POWER CHANGE







Available at

*Chargers and batteries come with a 3 year replacement warranty.

bunnings.co.nz

Ozito